


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Hodgeman County. Sec. 2 Twp. 21S Rge. 23W (E) (W)
Location as "NE/CNW/SW" or footage from lines 330' FSL & 330' FWL NE/4
Lease Owner Kewanee Oil Company
Lease Name Reinert Well No. 1
Office Address Box 360, Hoisington, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-8-1957
Application for plugging filed Yes 5-31-1957
Application for plugging approved Yes - File No. 16-25 6-3-1957
Plugging commenced 6-2-1957
Plugging completed 6-8-1957
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - Verbal permission

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4596 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	3788			9-5/8"	589'	0
Toronto	3804			5-1/2"	4567'	4024'
Douglas	3820					
Lansing-Kansas City	3838					
Marmaton	4208					
Penn. Basal Conglomerate	4450					
Mississippi	4465	4596				
Total Depth	4596					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into Total Depth 4596'
Plugging started 6-2-57. Finished 6-8-57.
Plugged off bottom with sand to 4450' and dumped 5 sacks cement with bailer.
Shot 5 1/2" casing at 4024'. Pulled pipe out of hole and plugged well with heavy mud to 500' and set permanent rock bridge. Dumped 20 sacks cement. Filled hole with heavy mud to 35' and mixed 10 sacks for cap on well. Well completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes dba Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Billy J. Patton (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Billy J. Patton
Box 360, Hoisington, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of June, 1957

Ernest W. Zulla
Notary Public.
STATE CORPORATION COMMISSION

My commission expires September 21, 1957

PLUGGING
FILE SEC 2 T 21 R 23W
BOOK PAGE 16 LINE 25

CONF. DIVISION
WICHITA, KANSAS

6-13-57

Well Record: Reinert No. 1

Location: 330' FSL and 330' FWL NE/4 Section 2, 21S, 23W, Hodgeman County, Kansas.

Operator: Kewanee Oil Company, Box 360, Hoisington, Kansas

Commenced: May 3, 1957

Completed: May 20, 1957 (Rotary)

Contractor: Graham-Michaelis Drilling Company, Wichita, Kansas

Casing Record: 9-5/8" @ 588.70 w/350 sacks Pozmix cement.
5-1/2" @ 4566.62' w/100 sacks Pozmix cement.

Shale-Sand-Lime Streaks	525
Blue Shale	591
Shale	867
Anhydrite	878
Shale	2345
Lime & Shale	3623
Lime	4450
Core #1	4475
Core #2 Miss.	4537
Lime & Chert	4596 RTD
TD Log	4594

Tops as follows:

Heebner	3788 (-1500)
Toronto	3804 (-1516)
Douglas	3820 (-1532)
Lansing KC	3838 (-1550)
Marmaton	4208 (-1920)
Conglomerate	4450 (-2162)
Mississippi	4465 (-2177)
T.D.	4594

Perforated: 4479-4484; 4467-4474 and 4465-4466

Acidized: Acidized w/750 Mudsol by Chemical Process.

Production: Well swabbed 100% water, no trace of oil after recovering load.

Temporary well record for plugger's information.

RECEIVED
STATE CORPORATION

JUL 5 1957

CONSERVATION DIVISION
Wichita, Kans.

PLUGGING			
FILE	SEC. 2	T. 21	23W
BOOK	PAGE 16	LINE 25	

Will file well
record later. We
do ^{not} have the
report from our
Geologist at the
present time.

KEWANEE OIL CO.,
P. O. Box 360
Hoisington Kansas

15.083.00033.0000