

Orig: State Corp. Comm.
 cc: B.A. Conner, 9th Floor Price Tower Mary Crump-Okla City
 STATE OF KANSAS WELL PLUGGING RECORD
 STATE CORPORATION COMMISSION K.A.R.-82-3-117
 200 Colorado Derby Building
 Wichita, Kansas 67202

15.083.20038.0001

Well File

API NUMBER 15-083-Prior to '67

LEASE NAME Kreider SWD

WELL NUMBER D01

SPOT LOCATION NE SW

SEC 12 TWP 21S RGE. 23 (E) or (W)

COUNTY Hodgeman

Date Well Completed 1968

Plugging Commenced 6-28-84

Plugging Completed 6-28-84

LEASE OPERATOR Phillips Petroleum Company

ADDRESS Box 287, Great Bend, Kansas 67530

PHONE # (316) 793-8421 OPERATORS LICENSE NO. 5229

Character of Well SWD
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? No If not, is well log attached? None available

Producing formation Cedar Hills Depth to top 1050 bottom 1150 T.D. 1144' PB

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface	Water	0	415	8 5/8	415'	-0-
Production	Oil & wtr	0	1170	5 1/2	1170'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. MIRU Hembree WSU. Rel pkr. COOH w/2 3/8" OD Duoline tbg. Rel WSU. MIRU B-J to 5 1/2" csg & plug as follows: Pmpd 2 sx hulls, mix 120 sx 50-50 Pozmix w/4% gel & 3% CaCl @ 900#. STP-500#. Rel B-J. State Rep Richard Lacey on location. (Note: This well has also been identified as the Hays AB D01)


(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B-J Cementing License No.
 Address Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

Kaare A. Westby, AGENT

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Kaare Westby
 Kaare A. Westby, Agent
 (Address) Box 287, Great Bend, Ks 67530

SUBSCRIBED AND SWORN TO before me this 11th day of July, 1984

Velma L. Mog
 Notary Public

My Commission expires: February 15, 1988

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 16 1984
 CONSERVATION DIVISION
 Wichita, Kansas