


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Blitting Building
Wichita, Kansas

Stafford County. Sec. 3 Twp. 21 Rge. (E) 12 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW NW
Lease Owner E. H. Adair
Lease Name Wolf Well No. 1-B
Office Address 407 W-K-H Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 11, 19 49
Application for plugging filed August 31, 19 49
Application for plugging approved August 31, 19 49
Plugging commenced August 31, 19 49
Plugging completed August 31, 19 49
Reason for abandonment of well or producing formation Barren

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Great Bend, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3474 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Copy of well log attached						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back 3422' dumped 5 sacks cement at 3422', mud to 250' bottom surface, 20 sx cement, mud to top-capped with 10 sacks cement.

RECEIVED
OCT 27 1949
CONSERVATION DIVISION
KANSAS

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to E. H. Adair Oil Company
Address 407 W-K-H Building
Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. H. Adair (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) *E. H. Adair*
Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of October, 19 49

My commission expires September 15, 1953

22-5138-s 9-48-10M

PLUGGING
FILE SEC 3 T 21 R 1 SW
BOOK PAGE 111 LINE 43

[Signature]
Notary Public.


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - E. H. ADAIR
Farm - Wolf "B" No. 1

SEC. 3 T. 21 R. 12W
NW NW NW

Total Depth. 3476 PB 3420
Comm. 8-1-49 Comp. 8-25-49
Shot or Treated.
Contractor.
Issued. 10-22-49

County. Stafford



Elevation. _____

Production. Dry

CASING:

8" 257'
5 1/2" 3420' cem w/100 sx.

Figures Indicate Bottom of Formations.

sand	140
shale	257
shale red sdy	282
shale	639
anhydrite	654
shale	1393
lime	1910
shale	1959
lime	2260
shale	2528
shale, shells	2636
shale	2805
lime	3421
conglomerate	3433
shale sdy	3470
arbuckle lime 2BWPB	3476
Total depth PB	3420

Tops:

Heebner	3048
Base Oread	3080
Br. Lime	3176
Lansing	3193
Base K. C.	3405
Marmaton	3417

Oil stain 3233-36
Trace spotted black oil 3322-30.
Slight Oil stain 3260-64.
Excellent odor and rainb.ow
@ 3417. Heavy live black oil
saturation.

RECEIVED
OCT 27 1949
STATE COMMISSION
KANSAS

PLUGGING
FILE SEC-3 T-21 R-12W
BOOK PAGE 111 LINE 43