


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 3 Twp. 21S Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines. Center SE SE SW
Lease Owner Duke & Wood Drilling Company
Lease Name Heim Well No. 1
Office Address Box 123, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 10 1953
Application for plugging filed April 17 1953
Application for plugging approved April 20 1953
Plugging commenced April 23 1953
Plugging completed April 23 1953
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3497 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	258	NONE
				5 1/2"	3470.22	2534.83

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole from total depth to 3340' with crushed rock, dumped 5 sacks of cement on same. Filled hole with heavy mud to 250', set 5 ft. rock bridge, dumped 20 sacks of cement on same. Filled hole with heavy mud to 35 ft., set 5 ft. rock bridge, dumped 10 sacks of cement on same, filled to bottom of cellar.

FILED
STATE CORPORATION COMMISSION

MAY - 5 1953

5-5-53

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Ace Pipe Pulling Company
Address Box 304, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Lynn O. Duke (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lynn O. Duke
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of April, 1953

My commission expires April 29, 1957



15.185.00195.0000

WELL LOG
Heim #1
SE SE SW of 3-21-12W
Stafford County, Kansas

Started: March 13, 1953
Completed: March 25, 1953

Elevation 1847 KB
Anhydrite 622 (-1225)
Heebner 3067 (-1220)
Lansing 3215 (-1368)
Arbuckle 3464 (-1617)
RTD 3473 (-1626)

0-195	Sand
195-250	Shale and red bed
250-622	Red bed
622-653	Anhydrite
653-1090	Shale and shells
1090-1190	Salt and shale
1190-1475	Shale and shells
1475-1665	Lime and shale
1665-1885	Lime and shale
1885-1940	Broken Lime
1940-1952	Sand
1952-2795	Lime and shale
2795-3050	Lime
3050-3140	Lime
3140-3205	Lime and shale
3205-3449	Lime
3449-3463	Shale
3463-3464	Sand
3464-3473	Arbuckle-Total rotary depth
3473-3497	Cable Tool Report
3497	Total Depth
	Arbuckle

A F F I D A V I T

STATE OF Kansas, COUNTY OF Barton, SS

I, Lynn O. Duke, of the DUKE & WOOD DRILLING COMPANY
being first duly sworn on oath, state; That I have knowledge of the facts,
statements and matters herein contained and that the same are true and correct.

PLUGGING
FILE SEC 3-121 R 12W
BOOK PAGE 94 LINE 15

Lynn O. Duke
Partner

Subscribed and sworn to before me this 17th day of April 1953.

RECEIVED
STATE CORPORATION COMMISSION

Dean T. Looley
Notary Public

APR 13 1953

My commission expires April 29, 1963 ON
Wichita, Kansas