


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 3 Twp. 21 Rge. 12 (E) W (W)  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines SW NE NW  
Lease Owner Inger Oil Co.  
Lease Name Wolf #7 Well No. \_\_\_\_\_  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 8-7-59 19\_\_\_\_  
Plugging completed 8-11-59 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Lackamp  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3449 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	223'	none
				5-1/2"	3430'	2792'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 3350' and found it open.  
Filled w/sand to 3340' and dumped 5 sacks of cement with bailer. Pulled 5 1/2" casing.  
Cleared hole and checked fluid to 60'. Bailed hole to 220' set rock bridge to 210' and dumped 20 sacks of cement. Mudded the hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cella.

RECEIVED  
STATE CORPORATION COMMISSION

PLUGGING COMPLETED

AUG 25 1959

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Knight Casing Pulling Co.  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.  
I, Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of August, 1959

My commission expires 9-27-62 Thomas V. Duggan Notary Public.

PLUGGING  
FILE SEC 3 T. 21 R. 12W  
BOOK PAGE 63 LINE 26

WICHITA COUNTY RECORDS DEPARTMENT  
 1001 N. W. CORNER  
 WICHITA, KANSAS

SEC. 3 T. 25 R. 12W  
 SE NW 1/4

Well No. 1260  
 Date 12-30-55  
 Operator  
 A. L. Jackson Drilling Co.  
 Well No. 1260

County WICHITA  
 KANSAS



7 5/8 2175  
 5 7/8 3125

Section 25

Section 25 BOYD, NW

Log of Well Bottom of Formation

hard clay		40
clay & sand		77
clay & shale		223
clay		265
red bed & shale		630
sandstone		555
shale & shells		1130
clay & shale		1290
shale & shells		1510
lime & shale		1610
sand		1630
lime & shale		2275
shale & shells		2480
lime & shale		2745
lime		3045
lime & shale		3175
brown lime		3184
shale		3189
K. C. lime		3220
lime		3425
lime & shale		3429
Arbuckle lime	RTD	3435
lime		3450
Total Depth		

TOPS:

Hebner	3045
brown lime	3175
Kansas City	3188
Arbuckle	3429

RECEIVED  
 STATE OF KANSAS  
 SEP 4 1955  
 CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING  
 FILE SEC. 3 T. 25 R. 12W  
 BOOK PAGE 63 LINE 26