


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Stafford County, Sec. 3 Twp. 21S Rge. 12 (E) (W) X

Location as "NE/CNW/SW" or footage from lines SE NE SE  
Lease Owner Aspen Drilling Company  
Lease Name Wolf "C" Well No. 1  
Office Address P. O. Box 783 Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 6-21-68 19  
Application for plugging approved 6-22-68 19  
Plugging commenced 9-1-68 19  
Plugging completed 9-30-68 19  
Reason for abandonment of well or producing formation



Locate well correctly on above  
Section Flat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren  
Producing formation Depth to top Bottom Total Depth of Well 3467 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	249	None
				5 1/2	None	2022

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 2 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Rigged up. Cleaned out cellar.

Sanded to 3440'. Dumped 5 sacks of cement. Working pipe. Shot pipe at 2930'.

Working pipe. Circulating. Spotted 65 bbl of oil.

Working pipe. Shot pipe at 2500' - 2300' - 2100' and 2020'. Pulling pipe.

Pushed plug to 249' rock bridge. Dumped 6 sacks of cement.

Bailing hole dry, at 240'. Dumped 20 sacks of cement. Mud hole and rock bridge. Capped well with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 1 day of October, 1968

My commission expires May 27, 1969

Notary Public.

D R I L L E R S   L O G

COMPANY: Aspen Drilling Co.  
 CONTRACTOR: Aspen Drilling Co.  
 LEASE NAME: Wolf 'C' #1  
 LOCATION: SE NE SE Sec.2-T21S-R12W  
 Stafford County, Kansas  
 ELEVATION: 1856 KB  
 SURFACE CASING: 6 jts. (241') 8 5/8"  
 OIL STRING: 110 jts. (3478.36') 5 1/2"  
 COMMENCED: 6-16-67  
 COMPLETED: 6-25-67  
 ROTARY TOTAL DEPTH: 3469'

<u>FORMATION</u>	<u>DEPTH</u>	
Red Bed	622	Ran 6 jts. (241') 8 5/8", set
Anhydrite	648	at 249', cemented with 250
Shale	1508	sacks Sunset. Cement circulated.
Shale-Lime	1545	
Lime-Shale	2120	DST #1                      3211-58
Shale	2235	DST #2                      3462-67
Shale-Lime	2850	
Lime-Shale	2950	Ran electric log.
Lime	3065	
Lime-Shale	3097	Ran 110 jts. (3478.36') 5 1/2",
Shale	3199	set at 3465'. Cemented with
Lime	3465	75 sacks.
Arbuckle	3469	
RTD	3469	

LOG TOPS

Anhydrite	622
Topeka	2808
Heebner	3063
Toronto	3082
Douglas	3096
Brown Lime	3197
Lansing	3210
Base KC	3421
Arbuckle	3461
Log TD	3467

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 2 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

AFFIDAVIT

State of Kansas        )  
                                   ) ss:  
 County of Barton     )

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

*William S. Schachle*  
 William S. Schachle

Subscribed and sworn to before me this 30th day of June, 1967.

*Theo. A. Holleman*  
 Theo. A. Holleman, Notary Public

My commission expires: April 18, 1968.