

WELL PLUGGING RECORD

FORMATION PLUGGING RECORD


STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Blitting Building Wichita, Kansas

Strike out upper line when reporting plugging off formations.

Stafford County. Sec 8 Twp 21 Rge 12 (X) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SW SE SW
Lease Owner: Petroleum, Inc.
Lease Name: Salem Well No. 1
Office Address: 100 Derby Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole): Lost Hole
Date well completed: December 18, 1950
Application for plugging filed: December 18, 1950
Application for plugging approved: December 18, 1950
Plugging commenced: December 18, 1950
Plugging completed: December 18, 1950
Reason for abandonment of well or producing formation: Lost Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production: 19...
Was permission obtained from the Conservation Division or its agents before plugging was commenced?: Yes

Name of Conservation Agent who supervised plugging of this well: Mr. C. D. Stough
Producing formation: Depth to top: Bottom: Total Depth of Well: 2760 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: 8 5/8", 248.87', None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to ... feet for each plug set.

Wooden plug set at 238'. Cemented and displaced through drill pipe 15 sax cement. Filled hole with heavy mud to 30'. Placed wooden plug at 30'. Filled hole to surface with cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 28 1950
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to: Petroleum, Inc.
Address: 100 Derby Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Eric H. Jager (employee of owner) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Eric H. Jager
100 Derby Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 26th day of December, 1950

Charlotte Heidman Notary Public

My commission expires October 13, 1954

PLUGGING
FILE SEC RT 7R 1X
BOOK PAGE 50 LINE 29

WELL LOG ON SALEM NO. 1

Petroleum, Inc., Lease Owner

Section 8, Twp. 21S, Rge. 12W

Garvey Oil, Contractor

Location: SW SE SW

Rotary Total Depth: 2750'

County: Stafford

Commenced: December 11, 1950

Elevation: 1861 D.F.

Completed: December 18, 1950

Casing: 248.87' of 8 5/8"

Figures below indicate bottom of formation:

205	Surface Soil and Sand
207	Sand
238	Shale & Shells
515	Red Bed
680	Anhydrite
1205	Shale & Shells
1515	Salt & Shale
1630	Br. Lime
1760	Lime
2000	Lime & Shale
2060	Br. Lime
2145	Shale
2370	Shale & Shells
2760	Lime & Shale
2760	R.T.D.

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

RECEIVED *Eric H. Jager*
STATE CORPORATION COMMISSION *Eric H. Jager*

DEC 28 1950

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS:
: SS.
SEDGWICK COUNTY:

Subscribed to and sworn to before me, a Notary Public in said County and State this 26th day of December, 1950.

PLUGGING
FILE SEC 8-11-R-120
BOOK PAGE 50 LINE 29

Charlotta Weidman
Notary Public

My commission expires: 10-13-54