

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Stafford County, Sec. 8, Twp. 21, Rge. 12 (E) (W)
SE SE SE

Location as "NE/CNWxSWx" or footage from lines _____
Lease Owner Sitrin Petroleum Corporation
Lease Name Salem #1 Well No. _____
Office Address Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 7/22/70 _____ 19____
Plugging completed 7/26/70 _____ 19____
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3495 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	285	none
				5 1/2"	3474	2784'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3495', ran sand, checked sand, bridge sand at 1700', loaded hole with water, ran sand pump, couldn't pump sand out, pumped bridge out with circulating pump. Shot pipe at 2880', 2790', pulled 87 joints. Pumped 15 sacks gel and 100 sacks of cement to plug well.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: KNIGHT CASING PULLING CO., INC.
Address: CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Chase, Kansas

(Address)

Subscribed and Sworn to before me this 5th day of August, 19 70

My commission expires 2/15/71

Margaret Melcher
Notary Public.

15.185.01394.0000

SALEM # 1 - SE SE SE Section 8-21a-12w Stafford County, Kansas
Company - S. A. Murphy.
Contractor - Virginia Drilling Co., Inc.
Commenced - October 12, 1964
Completed - October 26, 1964
Elevation - 1860 KB
Total Depth - 3495 1/2

8 5/8" set at 286 w/250 sx cm.
5 1/2" set at 3474 w/100 sx cm

FORMATION	DEPTH
Sand-gravel	0- 40
Sand - clay	40- 220
Redbed	220- 290
Shale-redbed	290- 655
Anhydrite	655- 680
Shale-shells	680-1500
Lime-shale	1500-1875
Lime	1875-2080
Lime-shale	2080-2980
Lime	2980-3113
Shale-lime	3113-3175
Lime	3175-3470
Lime-shale	3470-3481 RTD
C. Tools	3481-3495 1/2 TD

TOPS:

- 3090 - Hoebner
- 3110 - Toronto
- 3124 - Douglas
- 3218 - Brn Lime
- 3233 - Kansas City
- 3471 - Arbuckle

S. A. Murphy

Subscribed and sworn to before me, a Notary Public, this 17th day of November, 1964.

L. M. ...
Notary Public

My commission expires: 2-5-65

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1970
CONSERVATION DIVISION
Wichita, Kansas