


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD 15-145-30019-0000

Pawnee County. Sec. 31 Twp. 23s Rge. 15 ~~XXX~~ (W)

Location as "NE/CNW/SW" or footage from lines N/2 NW SW
Lease Owner Rock Island Oil & Refining Co., Inc.
Lease Name Thurrow Well No. 1
Office Address 321 West Douglas Avenue, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-13 1965
Application for plugging filed 5-13 1965
Application for plugging approved 5-13 1965
Plugging commenced 5-13 1965
Plugging completed 5-13 1965
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4213 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS.

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUR IN	PULLED OUT
				8 5/8"	240'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st Plug 420' - 20 sx cement through the drill pipe
2nd Plug 230' - 20 sx cement through the drill pipe
Top plug @ 35' - 1/2 sx Halls 10 sx cement 2 sx in Rat hole

RECEIVED
STATE CORPORATION COMMISSION

5-19-65 MAY 19 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address P. O. Box 486, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Leslie Kite

P. O. Box 486, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of May, 19 65

Ulanda Nichols

Ulanda Nichols

Notary Public.

My commission expires April 1, 1967

DRILLER'S LOG

15-145-30019-0000

COMPANY Rock Island Oil & Refining Co., Inc.
 CONTRACTOR LEBEN DRILLING, INC.
 FARM THURLOW #1
 LOCATION N/2 NW SW Sec. 31-23s-15W
 PAWNEE COUNTY, KANSAS
 COMMENCED 5-6-65
 COMPLETED 5-13-65

0	115	Clay, sand and gravel
115	360	Shale
360	993	Red Bed and Sand
993	1015	Anhydrite
1015	1357	Shale and Shell Rock
1357	1780	Shale and Sand
1780	1900	Shale and Lime
1900	2450	Lime and Shale
2450	3185	Shale and Lime
3185	3650	Lime and Shale
3650	4213	Lime
	4213	Rotary Total Depth - D & A

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 19 1965
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" surface casing @ 240' with 200 sx Posmix w/HA5

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Thurrow #1, located N/2 NW SW of Section 31, Township 23s, Range 15w, Pawnee County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite

 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 17th day of May, 1965.

Ulanda Nichols

 Ulanda Nichols

My Commission Expires: April 1, 1967