


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

7/24/68
HW

NORTH



Locate well correctly on above Section Plat

Pawnee County. Sec. 31 Twp. 23S Rge. 15 (E) W (W)
Location as "NE/CNW&SW" or footage from lines NE/4 NW/4 NW/4
Lease Owner Robert F. White
Lease Name Hill Well No. 1
Office Address 714 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1/3/68 _____ 19____
Plugging completed 1/9/68 _____ 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4131 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	gas and water	0	4129	5 1/2"	4129'	2394'
Surface casing		0	307'	8-5/8"	307'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Loaded hole with water, pushed plug to 3000', ran sand and 5 sacks of cement. Shot pipe at 2381', pipe came loose and pulled 77 joints. Pipe was full of mud, pumped mud from pipe with water truck. Squeezed well with 25 sacks of mud, 3 sacks of hulls and 100 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY, INC.
Address CHASE, KANSAS

STATE OF Kansas COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel Knight*
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of January, 1968

My commission expires February 15, 1971
Margaret Melcher
Notary Public.

15-145-00007-0001

LOG

Company: M. B. Armer
Contractor: M. B. Armer (Ideco Rig)
Drilling Commenced: 7/13/52
Drilling Completed: 7/25/52
Elevation: 2051 R.B.
2048 D.F.

Farm: Thurow (Hill) #1
Location: NE NW NW Sec. 31-23-15W
Pawnee County, Kansas
Casing Record: 8-5/8" casing at 307'
with 200 sacks cement.
5 1/2" casing at 4160' with 150
sacks cement.

(all figures below indicate bottoms)

Sand, Shells & Shale	128
Shale	307
Shale, Shells & Red Bed	600
Red Bed & Sand	960
Anhydrite	960
Red Bed Shale & Live Shale Sand	1400
Shale, Shells & Sand	1840
Lime & Shale	2655
Shale & Shells	2920
Shale & Lime Shells	3055
Shale & Lime	3360
Shale & Shells	3400
Shale & Lime	3630
Lime	3790
Lime & Shale	3828
Lime	3860
Shale & Lime	4015
Lime	4031
Shale	4063
Shale & Arbuckle Lime	4110
Lime	4160
R.T.D.	4160

FORMATION TOPS (R.B. Meas.)

Heebner	3495
Brown Lime	3626
Kansas City	3634
Viola	4010
Simpson	4036
Arbuckle	4074

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

M. B. ARMER

BY *C. P. Sproung*

STATE OF KANSAS)
) ss:
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a notary public, in and for said County and State this 29th day of July, 1952.

Shelton
Notary Public

My Commission expires Sept. 17, 1955.

RECEIVED
STATE COMMISSIONER
DEC 19 1961
CONSERVATION DIVISION
Topeka, Kansas