

15-145-01384-0000

R


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kan.

WELL PLUGGING RECORD

Pawnee County, Sec. 31 Twp. 23S Rge. 111111 15(W)

Location as "NE/CNW/SW" or footage from lines C - NW 1/4 NW 1/4 NE 1/4
Lease Owner Monsanto Chemical Company
Lease Name Gano Well No. 1
Office Address P. O. Box 580, Pratt, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed 6-13 19 52
Application for plugging filed 9-21 19 59
Application for plugging approved 9-23 19 59
Plugging commenced 10-8 19 59
Plugging completed 10-14 19 59
Reason for abandonment of well or producing formation Gas is sour - no available market since 1955.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production June 19 55
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Arbuckle Depth to top 4121 Bottom 4134 Total Depth of Well 4175 Feet
(P. B. T. D. 4134.5')
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	423'	0'
				5-1/2"	4165.5'	2144'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand from PBTB 4134.5' to 4100'.
Set 5 sacks cement plug from 4100' to 4060'.
Heavy mud from 4060' to 300'.
10' rock bridge plus 20 sacks cement from 300' to 230'.
Heavy mud from 230' to 40'.
10' rock bridge plus 10 sacks cement from 40' to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
OCT 16 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Box 304, Chase, Kansas

STATE OF KANSAS COUNTY OF PRATT, ss.
Bruce E. Roll (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bruce E. Roll
P. O. Box 580, Pratt, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of October, 19 59

My commission expires September 4, 1962 Van Dambek Notary Public.

15445-01384-0000

G-400-M-10E
SEC. 31-23-15W
PAWNEE COUNTY, KANSAS

GANO WELL No. 1

CONTRACTOR: THE R. W. RINE DRILLING COMPANY
STARTED: MAY 21, 1952

FINISHED: JUNE 6, 1952

LOG

SURFACE SAND	0	-	320	8-5/8" @ 422' w/300 sx. CEMENT
SAND AND SHALE	320	-	425	150# FLO-CELE AND 3. SX. C.C.
RED BED AND SHALE	425	-	935	SYFO @ 500' - OK
ANHYDRITE	935	-	945	
SHELS, SHALE AND LIME	945	-	1830	SYFO @ 1000' - OK. @ 1500' - 1/2".
LIME AND SHALE	1830	-	1960	
LIME	1960	-	2225	SYFO @ 2000' - 1/2".
LIME AND SHALE	2225	-	2375	
LIME	2375	-	2765	SYFO @ 2500' - 1".
LIME	2765	-	2895	
LIME AND SHALE	2895	-	3055	SYFO @ 3000' - 1".
LIME	3055	-	3135	
LIME AND SHALE	3135	-	3373	
LIME	3373	-	3460	
LIME	3460	-	3648	
LIME AND CHERT	3648	-	3675	
LIME	3675	-	3760	
LIME	3760	-	3898	
LIME AND SHALE	3898	-	3960	
CHERT AND LIME	3960	-	4045	
CHERT	4045	-	4051	
SHALE AND LIME	4051	-	4065	
CHERT	4065	-	4083	
LIME AND SHALE	4083	-	4097	
CHERT AND SHALE	4097	-	4125	
CHERTY LIME AND SHALE	4125	-	4150	
SHALE	4150	-	4160	
LIME AND ARBUCKLE	4160	-	4175	TD. 5 1/2" Csg. @ 4174' w/200 sx. BULK CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

SEP 22 1950

REGISTRATION DIVISION
Wichita, Kansas

I, R. M. GREEN, DO HEREDY CERTIFY THAT THE ABOVE IS A TRUE AND ACCURATE LOG OF THE GANO WELL No. 1, LOCATED CENTER NW, NW, NE, SECTION 31-23-15W, PAWNEE COUNTY, KANSAS.

R. M. Green
ASSISTANT SECRETARY

SUBSCRIBED TO AND SWORN BEFORE ME THIS 13TH DAY OF JUNE, 1952.

Leonard Pederson
NOTARY PUBLIC

MY COMMISSION EXPIRES APRIL 20, 1955.

PLUGGING

File Sec. 31 T 23 R 13W
Book Page 4 Line 9