


STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 Give All Information Completely  
 Make Required Affidavit  
 Mail or Deliver Report to:  
 Conservation Division  
 State Corporation Commission  
 211 No. Broadway  
 Wichita, Kansas

15-145-01457-0000

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Pawnee County. Sec. 32 Twp. 23 Rge. 15 (E)W. (W)  
 Location as "NE/CNWxSWx" or footage from lines. Gen. NE SW NE  
 Lease Owner Cities Service Oil Company  
 Lease Name Frick Well No. 1  
 Office Address Box 308, Great Bend, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Gas  
 Date well completed June 2 1963<sup>47</sup>  
 Application for plugging filed July 3 1963  
 Application for plugging approved July 8 1963  
 Plugging commenced July 13 1963  
 Plugging completed July 15 1963  
 Reason for abandonment of well or producing formation Depleted formation

If a producing well is abandoned, date of last production October 7 1960  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
 Producing formation Viola Depth to top 3979 Bottom 4029 Total Depth of Well 4152 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	373'	None
				5-1/2"	4152'	2020'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

4152-4060', bridge plug and 1-1/2 sacks cement.  
4060-3960', sand and 5 sacks cement.  
3960-377', mud and 18 sacks gel.  
377-300', 25 sacks cement.  
300-30', mud.  
30-0', 10 sacks cement.

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 25 1963

CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.  
 Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

John D. Forsyth (employee of owner) or owner of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John D. Forsyth

Box 308, Great Bend, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of July, 1963

Chas McFarland  
 Notary Public.

My commission expires December 6, 1966.

Company Cities Service Oil Co. Well No. 1 Farm Brick  
 Location 999' North and 990' East of Center Sec. 32 T. 23 R. 19W  
 Elevation 2031 (2028 A.) County Lawrence State Kansas  
 Drig. Comm. May 13, 1947 Contractor Corbett-Barbour Drilling Co.  
 Drig. Comp. June 2, 1947 Acid None  
 T. D. 4152' Initial Prod. Indicated Capacity: 40,500 M.C.F. gas (4 point B.P. test)

GRADING RECORD:

8-5/8" @ 373' with 250 lbs. cement.  
 5-1/2" @ 4152' with 350 lbs. cement.

FORMATION RECORD:

sand & clay	0-270
shale	273
red bed	940
anhydrite	975
shale	1190
shale & salt	1450
shells & shale	1650
shale	2015
shale & lime	2125
lime	2514
shale	2770
shale & lime	2860
shale	2950
lime & shale	3108
lime	3195
lime & shale	3390
lime	4010
cherty lime	4036
lime	4150

4150 Rot. TD = 4152 S.L.M.  
 Schlumberger

Top Lansing	3624'
Corr. Top Conglomerate	3960'
Corr. Top Viola	3985'
Corr. Top Simpson	4044'
Corr. Top Arbuckle	4080'
Penetration	72'
Total depth	4152'

Drilled cement to 4137 S.L.M.  
 Perforated 160 shots 4085-4125.

11,000 M.C.F. gas through 2" tubing

CLOGS TESTS (ACID BOTTLES):	500'	OK
	1000'	OK
	1500'	OK
	2000'	OK
	3000'	OK
	4000'	OK

**RECEIVED**  
 STATE CORPORATION COMMISSION

JUL 8 1963

CONSERVATION DIVISION  
 Wichita, Kansas