

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM

(File One Copy)

15-145-01389-000/

API NUMBER 12-22-52 (of this well)

6/86

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Cities Service Oil and Gas Corporation OPERATORS LICENSE NO. 5447

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112 PHONE # (405) 949-4400

LEASE (FARM) Benson Unit WELL NO. 206W WELL LOCATION SW SW NW COUNTY Pawnee

SEC. 32 TWP. 23S RGE. 15 ~~15~~ ^(W) TOTAL DEPTH 3870 PLUG BACK TD 3674

Check One:

OIL WELL _____ GAS WELL _____ D & A _____ SWD or INJ WELL X DOCKET NO. C-6115

SURFACE CASING SIZE 8-5/8" SET AT 369 CEMENTED WITH 200 SACKS

CASING SIZE 5-1/2" SET AT 3870 CEMENTED WITH 150 SACKS

PERFORATED AT 3603-3657

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL _____

(See Attachment)

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? no
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 12-1-85

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Earl Rollings PHONE # (316) 672-9388

ADDRESS Box 381 Pratt, Kansas 67124

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050

ADDRESS Box 347 Chase, Kansas 67524 PHONE # (316) 938-2457

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Raymond Hui

Kelso Casing Pulling
STATE CORPORATION COMMISSION

(Operator or Agent)

DATE: 11-7-85

11-14-85 NOV 14 1985

15-149-01389-0001

**PLUGGING PROCEDURE
FOR BENSON UNIT WELLS**

1. Dump sand of sufficient quantity to cover perforations fifty (50) feet.
2. Place five (5) sacks cement on sand using dump bailer prior to pulling pipe.
3. Run freepoint. Shoot off 5-1/2" casing and pull same.
4. Pump down 8-5/8" surface pipe as follows:
 - A. 3 sacks hulls
 - B. 50 sacks cement
 - C. 10 sacks gel
 - D. 30-50 sacks cement
 - E. 8 sacks gel
 - F. 1 sack hulls
 - G. 8-5/8" wiper plug
 - H. Appropriate volume of cement to fill surface pipe above plug (\pm 120 sacks)
5. Cut off 8-5/8" three (3) feet below ground level and verify surface casing is filled with cement.

The above procedure recommended by Paul Luthi of the Dodge City, Kansas Corporation Commission Office.

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1935

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas



JOHN CARLIN
CHAEL LENNEN
MARGALEE WRIGHT
JITH R. HENLEY
DITH A. McCONNELL
MIAN J. MCLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

FEB 14 1986

EXPIRES

November 14, 1985

WELL PLUGGING NOTICE

15-145-01389-0001

Benson Unit #206W (SWD)
SW SW NW
Sec. 32-23S-15W
Pawnee County

Cities Service Oil & Gas Corporation
3545 NW 58th Street
Oklahoma City, OK 73112

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson

William R. Bryson, Director

Please submit your proposal for plugging the above captioned well to
DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760

five days prior to plugging the well (KAR-82-3-113).