

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER K-149-01388-0000

LEASE NAME Benson Unit #205

WELL NUMBER _____

SPOT LOCATION NE SW NW

SEC. 32 TWP. 23 SRGE. 15w (E) or (W) (W)

COUNTY Pawnee

Date Well Completed _____

Plugging Commenced 1/15/86

Plugging Completed 1/21/86

LEASE OPERATOR Kelso Casing bought f/ Cities Service Oil & Gas

ADDRESS Box 347, Chase, Ks. 67524

PHONE # (316) 938-2457 OPERATORS LICENSE NO. 6050

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, Is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 3923'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	392'	none
				5 1/2"	3903'	2490'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged bottom with sand to 3500' & 5 sacks cement. Shot pipe at 2490'.

Pulled 79 joints of pipe. Plugged well with 4 hulls, 20 gel, & 200 sacks 60/40 poz 6% gel.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 14th day of February, 19 86

Irene Hoover
Notary Public

My Commission expires: _____



FEB 18 1986 2-18-86

**PLUGGING PROCEDURE
FOR BENSON UNIT WELLS**

15-145-01388-0000

1. Dump sand of sufficient quantity to cover perforations fifty (50) feet.
2. Place five (5) sacks cement on sand using dump bailer prior to pulling pipe.
3. Run freepoint. Shoot off 5-1/2" casing and pull same.
4. Pump down 8-5/8" surface pipe as follows:
 - A. 3 sacks hulls
 - B. 50 sacks cement
 - C. 10 sacks gel
 - D. 30-50 sacks cement
 - E. 8 sacks gel
 - F. 1 sack hulls
 - G. 8-5/8" wiper plug
 - H. Appropriate volume of cement to fill surface pipe above plug (\pm 120 sacks)
5. Cut off 8-5/8" three (3) feet below ground level and verify surface casing is filled with cement.

The above procedure recommended by Paul Luthi of the Dodge City, Kansas Corporation Commission Office.

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1955

CONSERVATION DIVISION
Wichita, Kansas