


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittig Building  
Wichita, Kansas

Pawnee County, Sec. 32, Twp. 23, Rge. 15 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SW SW  
Lease Owner BUICK DRILLING INC.  
Lease Name Campbell Well No. 1  
Office Address Box 331, St. John, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Sept. 13, 1952  
Application for plugging filed Sept. 13, 1952  
Application for plugging approved Sept. 13, 1952  
Plugging commenced Sept. 13, 1952  
Plugging completed Sept. 13, 1952  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough  
Producing formation None Depth to top - Bottom - Total Depth of Well 4190 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	262	8 5/8	262	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4190' back to 262' heavy rotary mud plug with 20 sacks cement placed through drill pipe. 262' to 40' heavy rotary mud, with plug and 15 sacks cement placed through drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Buick Drilling Inc.  
Address Box 331  
St. John, Kansas

STATE OF Kansas, COUNTY OF Stafford, ss.  
H. R. Buick (employee or owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *H. R. Buick*

St. John, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 16 th day of September, 1952

My commission expires December 26, 1955

*Roberta Shogren*  
Notary Public.



23-8390-s 6-51-20M STATE CORPORATION COMMISSION

SEP 12 1952 9-18-52

CONSERVATION DIVISION

DRILLERS' LOG

15-145-600B-6000

Campbell #1

NE SW SW

Sec. 32-23-15W

Commenced R.D.: 8-30-52

Pawnee County, Kansas

Completed R.D.: 9-13-52

Elevation: 2035 D.F.

Total Depth: 4190'

Initial Prod.: Kansas City

Casing Record: 262' of 8 5/8"

Contractor: Buick Drilling Inc.

STRATA	DEPTH
Surface Clay and Sand	0 - 40
Sand and Gravel	40 - 140
Shale	140 - 260
Red Bed and Shale	260 - 455
Sand	455 - 516
Red Bed and Shale	516 - 968
Anhydrite	968 - 995
Shale and Shells	995 - 1900
Lime and Shale	1900 - 3595
Lime	3595 - 3602
Shale and Sand - iron streaks	3602 - 3655
Lime and Shale	3655 - 3740
Lime	3740 - 4040
Lime and Chert	4040 - 4100
Chert, Lime, and Shale	4100 - 4135
Lime and Shale	4135 - 4190 T.D.

I hereby certify the above a true and correct drilling log as reflected by the drilling reports of the Buick Drilling Inc.

BUICK DRILLING INC.

*H. R. Buick*

H. R. Buick, President

Signed and sworn to in my presence this 16th day of September, 1952, by H. R. Buick, President of the Buick Drilling Inc.

*Roberta Shogren*

Notary Public

My Commission Expires December 26, 1955

PLUGGING  
 FILED SEC 23 T 23 R 152  
 ECOK PAGE 46 LINE 46

RECEIVED  
 THE COMMISSION  
 SEP 12 1952  
 CONSERVATION DIVISION