


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Pawnee County, Sec. 33 Twp. 23 Rge. 15 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW SE SW
Lease Owner Aspen Drilling Co.
Lease Name Becker Well No. 1
Office Address P. O. Box 783 ; Great Bend, Ks. 67530
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed July 19 74
Application for plugging approved July 19 74
Plugging commenced July 10 19 74
Plugging completed July 24 19 74
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	252	None
				5 1/2"	2238	1705

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


July 10, 1974 Plugged off bottom. Dumped sand to 2050'. Mixed and dumped 5 sx of cement.
July 24, 1974 Plugged off top. Sun Oil Well Cementing Co. mixed and pumped down 8 5/8" surface casing; 3 sx of hulls, 20 sx of gel and 100 sx of cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor RUSS CASING PULLING, INC.
Address P. O. Box 1082 ; Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
Robert L. Pelster (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Robert L. Pelster, Great Bend, Kansas
(Address)



Subscribed and Sworn to before me this 10th day of September, 19 74
Theora Holleman
Notary Public

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors

1008 UNION NATIONAL BUILDING
WICHITA, KANSAS 67202

April 2, 1973

15-145-20288-0000

Company;	Aspen Drilling Co.
Farm;	#1 Becker
Location;	NW SE SW
Section;	33-23-15W
County;	Pawnee
Contractor;	Woodman & Iannitti Drilling Co.
Comm;	March 22, 1973
Compl;	March 30, 1973
Total Depth;	2961'
Casing;	8 5/8" @ 252 w/200 sx 5 1/2" @ 2238 w/125 sx

Figures Indicate Bottom Of Formations:

190	Sand
252	Shale
435	Shale
475	Sand
850	Shale & Red Bed
950	Red Bed
976	Anhy
1560	Shale & Shells
1860	Shale & Shells
1955	Lime & Shale
2005	Lime
2025	Lime
2040	Lime
2100	Lime
2185	Lime
2315	Shale & Lime
2451	Lime & Shale
2510	Lime & Shale
2526	Lime
2580	Shale & Lime Streaks
2640	Lime
2690	Lime
2800	Lime & Shale
2890	Lime
2961	Lime

RECEIVED
STATE CORPORATION COMMISSION
JUL 8 1974
CONSERVATION DIVISION
Wichita, Kansas

Woodman & Iannitti Drilling Co.

[Signature]
K. T. Woodman

BECKER
#1
Top Com
1802

PBTD 3150

Original mailed to NNG 4/3/73.

Copy to American 4-18