

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-145-21,317-0000

LEASE NAME Evans

WELL NUMBER #1

660 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 34 TWP. 23 RGE. 15 (E) or (W)

COUNTY Pawnee

Date Well Completed _____

Plugging Commenced 10-15-90

Plugging Completed 10-23-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Pintail Petroleum, LTD.

ADDRESS 412 E. Douglas, Suite One, Wichita, Ks. 67202

PHONE # (316) 687-3450 OPERATORS LICENSE NO. 5086

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 12, 1990 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4115'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	304'	None
				4-1/2"	4112'	425.95'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Dumped sand to 3950 and 4 sacks cement. Shot casing at 3321', 3001'-2723' and 2518'. Pulled 11 joints of 4-1/2" casing. Howco plugged well with 300 # hulls, 10 sacks gel. 50 sacks cement, 10 sacks gel. 100# hulls and 150 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 500 psi and shutin 350 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Ks. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pintail Petroleum, LTD.

STATE OF Kansas COUNTY OF Barton, ss.

OCT 26 1990

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold
 Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 25th day of October, 1990

My Commission Expires:

IONA M. LEATHERMAN
 Barton County, Kansas
 My Appt. Exp. 9-26-91

Iona M. Leatherman
 Notary Public