

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
209 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-145-21,316-0000

LEASE NAME DORAN

WELL NUMBER 34-1

2970 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 34 TWP. 23 RGE. 15 (X) or (W)

COUNTY Pawnee

Date Well Completed 3-27-90

Plugging Commenced 3-27-90

Plugging Completed 3-28-90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Pintail Petroleum

ADDRESS 412 E. Douglas, Suite One, Wichita, KS 67202

PHONE#(316) 263-2243 OPERATORS LICENSE NO. 5086

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-27-90 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4133'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface		353'	0'	8-5/8"	353'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Plugged w/ 125 sacks 60/40 Pozmix, 6% gel as follows: 50 sx @ 980', 40 sx @ 390', 10 sx @ 40', 15 sx R.H., 10 sx M.H. P.D. @ 1:00 a.m. 3-28-90.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4958

Address P.O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pintail Petroleum


STATE OF KANSAS COUNTY OF SEDGWICK, ss. SUL 12 1990

Walter I. Phillips, Jr. (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Walter I. Phillips, Jr.

(Address) 412 E. Douglas, #1, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 20th day of May, 19 90



My Commission Expires: 12/11/93

Notary Public  
Patricia C. Byerlee

MALLARD JV, INC.  
P.O. BOX 1009  
McPHERSON, KS 67460

15-145-21316-0000

DRILLERS' LOG

OPERATOR: Pintail Petroleum  
412 E. Douglas, Suite One  
Wichita, KS 67202

WELL: Doran #34-1

API#: 15-145-21,316

COMMENCED: March 22, 1990

LOCATION: SW SW NE

COMPLETED: March 28, 1990

2970 Ft. FSL, 2310 Ft. FEL

TOTAL DEPTH: 4133 Ft.

SEC. 34 TWP. 23 S RGE. 15 W

ELEVATION: 2020 Ft. G.L.

COUNTY: Pawnee

2028 Ft. K.B.

\*\*\*\*\*

D & A - Simpson Formation

REMARKS

Cut 12 1/4" hole to 355' and ran 8 joints 8-5/8" x 20# x 342.86' surface casing. Set at 353.46' and cemented with 190 sacks 60/40 Pozmix, 2% gel, 3% cc. Cement did circulate. P.D. @ 9:45 p.m. 3-22-90.

Ran 1 DST.

Drilled 7-7/8" hole to 4133' and plugged with 125 sacks 60/40 Pozmix, 6% gel as follows:

- 50 sx @ 980'
- 40 sx @ 390'
- 10 sx @ 40'
- 15 sx R.H., 10 sx M.H.
- P.D. @ 1:00 a.m. 3-28-90

RECEIVED  
STATE CORPORATION COMMISSION

APR 12 1990

\*\*\*\*\*

STATE OF KANSAS )  
COUNTY OF MCPHERSON ) SS:

CONSERVATION DIVISION  
Wichita, Kansas

I, Dick Hess of MALLARD JV, INC. hereby certify that this is a true and correct copy of the log of the Doran #34-1 well as reflected by the files of Mallard JV, Inc.

*Dick Hess*

Subscribed and sworn to before me this 3rd day of April, 1990.



*Bryan K Hess*  
NOTARY PUBLIC