


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-145-26501-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County, Sec. 34 Twp. 23 Rge. 15 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C NW/4 NW/4 SE/4
Lease Owner Barnett Oil, Inc.
Lease Name Doran-Evans Well No. 1
Office Address 1625 Vickers KSB Bldg. Wichita, Ks 67202
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole
Date Well completed March 29 1978
Application for plugging filed March 29 1978
Application for plugging approved March 29 1978
Plugging commenced 9:30 P. M. March 29 1978
Plugging completed March 29 1978
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4190
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole W/mud, pumped 50 sx 50/50 Pozmix W/2% Gel thru open end DP at 420'
Mud to 240' pumped 25 sx thru open end DP
Mud to 40', 1/2 sack hulls and wood plug for solid bridge
Pumped 10 sx to surface 2 sx in rathole

RECEIVED
STATE CORPORATION COMMISSION
APR 03 1978

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Allied 4-378

STATE OF Kansas COUNTY OF Barton, ss.
Gary Bagby (employee of owner) or ~~(owner or operator)~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gary Bagby
Gary Bagby Sterling, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of March, 19 78

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY COM. EXPIRES 5-20-81

Bessie M. Dewerff
Bessie M. Dewerff Notary Public.

My commission expires

DRILLERS WELL LOG

L. D. DRILLING COMPANY - CONTRACTOR BARNETT OIL, INC. - OPERATOR

DORAN-EVANS # 1
 C NW/4 NW/4 SE/4 34-23S-15W
 PAWNEE COUNTY, KANSAS

ELEV. 2015 KB
 T.D. 4190

COMMENCED: 3-20-78
 COMPLETED: 3-21-78

CASING

8-5/8" set at 337'

CEMENT

275 sx Common, 2% gel, 3% CC

FORMATION

Sand & clay
 Shale & sand
 Red Beds
 Sand
 Red Beds
 Anhy.
 Shale & Shells
 Shale & Lime
 Lime & Shale
 Shale
 Lime & Shale
 Cherty Shale & Lime
 Cherty Shale & Sand
 Dolomite

DEPTH

0 - 75
 75 - 265
 265 - 435
 435 - 495
 495 - 945
 945 - 965
 965 - 2630
 2630 - 3032
 3031 - 3551
 3551 - 3647
 3647 - 3992
 3992 - 4011
 4011 - 4164
 4164 - 4190

TOPS

Dakota 435
 Anhydrite 945
 Fort Riley 2630
 Admire 2712
 Waubensee 2772
 Langdon 2829
 Tarkio 2902
 Howard 3032
 Heebner 3511
 Toronto 3532
 Douglas 3551
 Brown Lime 3647
 Lansing 3658
 Base K/C 3898
 Conglomerate Shale 3992
 Conglomerate Chert 4011
 Simpson 4124
 Arbuckle 4164
 R.T.D. 4190

RECEIVED
 STATE COMMISSION
 APR 03 1978
 PAWNEE COUNTY, KANSAS

AFFIDAVIT

State of Kansas County of Barton

I, Gary Bagby of the L. D. Drilling Company

being first duly sworn on oath, State: That I have knowledge of the facts statements and matters herein contained and that the same are true and correct.

Gary Bagby
 Gary Bagby

Subscribed and sworn to before me on this 31st day of March 1978

BESSIE M. DEWERFF
 STATE NOTARY PUBLIC
 BARTON COUNTY, KANSAS
 MY COM. EXPIRES 3-20-81

Bessie M. DeWerff
 Notary Public: Bessie M. DeWerff