

15-145-20468-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County, Sec. 34 Twp. 23S Rge. 15W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
NW NW NW

Lease Owner Barnett Oil, Inc.
Lease Name Mackey #1 Well No. 1
Office Address 1625 Vickers KSB Building, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed May 18, 1977 19
Application for plugging filed May 18, 1977 19
Application for plugging approved May 18, 1977 19
Plugging commenced 7:00 PM, May 18, 1977 19
Plugging completed 9:15 PM, May 18, 1977 19
Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation Depth to top Bottom Total Depth of Well 4194'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	327'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy Mud.
Rig Pumped thru open ended drill pipe 50 sacks at 420'; 25 sacks at 240'; solid bridge with plug and 1/4 sacks hulls at 40'; 10 sacks to surface; 2 sacks in rathole.

RECEIVED
STATE CORPORATION COMMISSION

MAY 25 1977

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Whellner (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY


(Signature) F. A. Whellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of May, 1977

CHARLES HALL—NOTARY PUBLIC
My Commission Expires Jan. 6, 1978

Charles M. Hall, Notary Public.

My commission expires



STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

15-145-70468-0000

WELL LOG ----- MACKEY #1
Located: NW NW NW, Section 34-23S-15W, Pawnee County, Kansas

OWNER: Barnett Oil, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 11, 1977
COMPLETED: May 16, 1977

TOTAL DEPTH: 4194'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 135 Sand and Clay	Ran 8 joints used 28# 8 5/8" casing,
135 - 285 Shale	315.73' set at 327' K.B. with 250 sacks
285 - 330 Red Bed	Common with 2% gel and 3% cc. Plug down
330 - 500 Shale, Sand, Red Bed	at 9:30 PM, 5-11-77, by Allied.
500 - 949 Red Bed and Sand	
949 - 969 Anhydrite	
969 - 1610 Shale and Shells, Salt	
1610 - 1957 Salt, Shale, Lime	
1957 - 3685 Lime and Shale	
3685 - 3780 Lime	
3780 - 3865 Lime and Shale	
3865 - 4025 Lime	
4025 - 4120 Lime, Shale, Chert	
4120 - 4172 Lime and Shale	
4172 - 4194 Anhydrite	Plugged.

RECEIVED
STATE CORPORATION COMMISSION

MAY 25 1977

CONSERVATION DIVISION
Wichita, Kansas