

15-145-00470-0000

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pawnee County. Sec. 34 Twp. 23 Rge. ~~15~~ 15(W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SW $\frac{1}{4}$ 660' from S line and

Lease Owner Mid-Continent Petroleum Corp. 330' from W line.

Lease Name Anna Redetzke Well No. 1

Office Address Box 1362, Wichita 1, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 21, 19. 48

Application for plugging filed Verbal request, May 21, 19. 48

Application for plugging approved May 21, 19. 48

Plugging commenced May 21, 19. 48

Plugging completed May 21, 19. 48

Reason for abandonment of well or producing formation Well completed as a Dry Hole.

If a producing well is abandoned, date of last production 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C.D. Stough.

Producing formation None Depth to top Bottom Total Depth of Well 4230' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
KC Lansing Lime	water	3668'	4000'	8 5/8	3.05'	none
Viola Chert		4023'	4116'			
Arbuckle Lime	water	4188'	4230'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy mud from 4230' to 300'- Wooden plug drove with drill pipe to 300' and cemented with 15 sacks of cement from 300' to 252'- Hole filled with heavy mud from 252' to 39' and wooden plug drove with drill pipe to 39' and cemented with 10 sacks of cement from 39' to 7' (. top of surface casing) Cellar to be filled to ground level.

Lloyd Snyder
5-27-48

MAY 27 1948

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mr. Lloyd Snyder, Box 1362, Wichita 1, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.

A. E. Johnson (employee of owner) or (owner) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *A. E. Johnson*

R.R. # 1, Ellinwood, Kansas.

(Address)

SUBSCRIBED AND SWORN to before me this 24th day of May, 1948.

My commission expires Oct 28 - 1948

22-237 7-47-10M

Philo Liberty
Notary Public.

PLUGGING
FILE SEC 34 T 23 R 15W
BOOK PAGE 21 LINE 30

15-145-00470-0000

COMPANY - Mid-Continent Petroleum Corp.
 WELL - Anna Redetzke No. 1

Sec. 34 T. 23S R. 15W
 C W L SW SW

Total Depth - 4230'
 Comm. 5-5-48 Comp. 5-21-48
 Shot or treated
 Contractor - Barnett Drilling, Inc.

COUNTY - Pawnee
 Elevation 2014'

CASING:
 8 5/8" 28" S.H.L.W. 298'

Production Dry

Clay	0	40
Sand	40	75
Gravel	75	100
Clay	100	240
Shale & clay	240	288
Red bed	288	305
Red bed, shale & shells	305	425
Red bed	425	535
Red bed & shale	535	820
Sandy red bed	820	855
Red bed & shale	855	940
Lime, Anhydrite	940	975
Shale & shells	975	1815
Lime & shale	1815	2035
Lime	2035	2095
Shale	2095	2130
Shale & lime	2130	2275
Lime	2275	2335
Sandy lime & shale	2335	2355
Shale & lime	2355	2975
Shale	2975	3025
Lime	3025	3070
Shale & lime	3070	3220
Lime	3220	3615
Shale & lime	3615	3660
Lime	3660	3668
Lime, K.C. Lansing	3668	4000
Conglomerate	4000	4023
Chert, Viola	4023	4116
Shale, Simpson	4116	4128
Conglomerate	4128	4143
Shale, lime & chert	4143	4188
Lime, Arbuckle	4188	4230
TOTAL DEPTH	4230 ✓	

SCHLUMBERGER TOPS

Brown lime	3660
Lansing lime	3668
Viola lime	4023
Simpson shale	4116
Conglomerate	4128
Arbuckle	4188 ✓

MAY 27 1948