

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-145-30004-0002

LEASE NAME Grizzell

WELL NUMBER 1-23

460' AP NE SW SW SE  
Ft. from S Section Line

2110' Ft. from E Section Line

SEC. 23 TWP. 23 RGE. 15 (E) or (W)

COUNTY Pawnee

Date Well Completed 2/12/68

Plugging Commenced 05/06/02

Plugging Completed 05/08/02

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

MAY 13 2002

KCC WICHITA

LEASE OPERATOR Deutsch Oil Company

ADDRESS 8100 E 22nd St N, Bld 600, Ste D, Wichita, KS 67226

PHONE (316) 681-3567 OPERATORS LICENSE NO. 3180

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 05/03/02 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached?

Producing Formation \_\_\_\_\_ Depth to Top 2089' Bottom 4150' T.D. 4275'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0'	221'	8-5/8"	221'	0'
	Production	0'	4150'	5-1/2"	4150'	832.95'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Bottom plug. Sanded well back to 2039', 5 sx cement. Set jacks and pull stretch into pipe. Run knife in and cut casing off at 860'. Pull to 830'. spot 10 sx gel and 50 sx cement. Pulled to 280'. spot 50 sx cement. Pulled to 40'. pump 40 sx cement to surface. Pulled pipe out. Well stayed full. Tore down jacks. Rigged down and moved off.


Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, KS 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Deutsch Oil Company

STATE OF Kansas COUNTY OF Barton, ss.

Joseph F. Strube (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

 KAREN J. MITCHELL  
Notary Public - State of Kansas  
My Appt. Expires 4/13/06

(Signature) Joseph F. Strube  
(Address) P.O. Box 231, Claflin, KS 67525

SUBSCRIBED AND SWORN TO before me this 9th day of May, 2002

Karen J. Mitchell  
Notary Public

My Commission Expires: April 13, 2006

OR