


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County, Sec. 23 Twp. 23S Rge. 15W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
SE NE NE

Lease Owner Alpine Drilling Co., Inc.
Lease Name Grizzell Well No. B-1
Office Address 200 E. First, Suite 500, Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed January 30 19 80
Application for plugging filed January 30 19 80
Application for plugging approved January 30 19 80
Plugging commenced January 30 19 80
Plugging completed January 30 19 80
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4094
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|------|--------|------------|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Plugged as follows:
Filled hole w/mud, pumped 60 sx 50/50 pozmix, 4% gely
thru open end D.P. @ 540'; mud to 300'; pumped 30 sx
thru open end D.P., mud to 40'; 1/2 sx hulls & wood
plug for solid bridge, pumped 10 sx to base of cellar
5 sx in rathole, completed @ 2 p.m. 1-30-80 by Allied
Witnessed: Marion Schmidt, State Plugger, Hays, Kansas
Gary Bagby, Sterling, Kansas

2-4-80

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Husky Drilling Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Jon T. Williams, Jr. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God

(Signature) *Jon T. Williams, Jr.*
200 E. First, Suite 500, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of February, 19 80

Geraldine Stewart
STATE NOTARY PUBLIC
Sedgewick County, Kansas
My Commission Expires January 12, 1981

Geraldine Stewart
Geraldine Stewart Notary Public.



200 E. First, Suite 500
~~800 Broadway Blvd~~
 Wichita, Kansas 67202
 Phone 316 - 263-7904
 Mobile Phone 316 - 793-7859 Unit 7070

15-145-206480000

February 1, 1980

WELL LOG-----Grizzell-B No. 1
 Located: SE NE NE of Sec.23-23S-15W, Pawnee Co., KS

OWNER: Alpine Drilling Co., Inc.
 ROTARY CONTRACTOR: Husky Drilling Co., Inc.

COMMENCED: January 22, 1980
 COMPLETED: January 30, 1980

Rotary Total Depth: 4094'

| <u>LOG</u> | <u>CASING RECORD</u> |
|---------------------------|------------------------------------|
| 0 - 155 Sand | Ran 11 jts., used 8-5/8", 28#, 8V, |
| 155 - 280 Shale | Rge 2, tallied 361' set @ 368' KB |
| 280 - 371 Red Bed | w/275 sx common, 2% gel, 3% cc, |
| 371 - 918 Red Bed - Sand | circ, plug down @ 4:30 p.m. by |
| 918 - 939 Anhydrite | Allied 1-22-80. |
| 939 - 1500 Shale & shells | |
| 1500 - 3700 Shale & lime | |
| 3700 - 3965 Lime | |
| 3965 - 4094 Lime & Shale | Plugged & Abandoned 1-30-80 |

RECEIVED
 STATE GEOLOGICAL COMMISSION
 FEB - 4 1980
 CONSERVATION DIVISION
 Wichita, Kansas