


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 24 Twp. 23S Rge. 15W (E) (W)
Location as "NE/CNW%SW%" or footage from lines. SE NE SE
Lease Owner Leben Drilling, Inc.
Lease Name Crissman Well No. 1
Office Address Box 486, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-4-65 19
Application for plugging filed 6-4-65 19
Application for plugging approved 6-4-65 19
Plugging commenced 6-4-65 19
Plugging completed 6-4-65 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4027 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	273'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud, pumped plug and 100 sks. 50-50 Posmix down 8 5/8" casing, 450# pressure

RECEIVED
STATE CORPORATION COMMISSION

JUN 11 1965

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet) Wichita, Kansas

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Leslie Kite

P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of June, 1965

Mauda Nichols
Notary Public.

My commission expires April 1, 1967

DRILLER'S LOG

15-145-30017-0000

COMPANY: Leben Drilling, Inc.
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: CRISSMAN #1
 LOCATION: SE NE SE Sec. 24-23S-15W
 STAFFORD COUNTY, KANSAS
 COMMENCED: 5-26-65
 COMPLETED: 6-4-65

0	90	Sand
90	200	Shale & Sand
200	273	Shale & Shells
273	350	Shale
350	911	Red Shale & Shells
911	940	Anhydrite
940	1960	Shale & Shells
1960	2343	Lime
2343	2632	Lime & Shale
2632	3280	Shale & Lime
3280	3965	Lime
3965	4027	Lime, trace of Chert
	<u>4027</u>	<u>RTD - D. & A.</u>

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 11 1965
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" used surface casing @ 273' cemented with 225 sacks
 60-40 Posmix Sunset 2% Gel

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Crissman #1 well, located SE NE SE Sec. 24, Township 23 South, Range 15 West, of Stafford County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 10th day of June, 1965.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:
 April 1, 1967