


15-145-00520-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Palmer County. Sec. 25 Twp. 23 Rge. (E) 15 (W)
Location as "NE/CNWxSWx" or footage from lines SW NE NE
Lease Owner D. R. Lanck Oil Co., Inc.
Lease Name Guyer Well No. 7
Office Address 301 S. Broadway Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed October 23 19 64
Application for plugging filed September 30 19 71
Application for plugging approved October 4 19 71
Plugging commenced October 23 19 71
Plugging completed November 24 19 71
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production September 30 1971
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Leo Massey
Producing formation Lansing Depth to top 3602 Bottom 3866 Total Depth of Well 4141 Feet
Show depth and thickness of all water, oil and gas formations. PB 4086

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing	Oil	3602	3866	8 5/8	255	None
Viola	Dry	3963	4025	5 1/2	4140	
Simpson	Dry	4025	4065			
Arbuckle	Dry	4065	4140			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 3800'
5 sacks cement 3800' to 3770'
Pumped 3 sacks hulls, 20 sacks Jel mud, and 100 sacks cement to plug well.

RECEIVED
STATE CORPORATION COMMISSION
DEC 6 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glenn & Smith Pupe Pulling Co.
Address Box 156 Ellinwood, Kansas 67526


STATE OF _____, COUNTY OF _____, ss.
_____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
P. O. Box 188 Ellinwood, Kansas 67526
(Address)

SUBSCRIBED AND SWORN to before me this 3 day of December, 19 71

[Signature]
Notary Public.

March 6, 1972



15-145-00520-0000

D. R. Lauck Oil Company, Inc.

Guyer #1

SW NE NE Sec. 25-23S-15W
Pawnee County, Kansas

Commenced: October 7, 1964
Completed: October 17, 1964

Casing Record: 257' 8-5/8" Cemented with 180 sacks Cement,
4 sacks Calcium Chloride.
4140' 5-1/2" Cemented with 1350 gallons Latex Cement.

Elevation: 1992 GL; 1994 DF; 1996 KB;

Drillers Log

Tops

		Sample	Electra
Clay & Sand	205	920+1076	920+1076
Blue Shale	257	Heebner	3466-1470 3465-1469
Shale & Red Bed	375	Toronto	3487-1491 3488-1492
Sand	450	Douglas	3507-1511 3508-1512
Red Bed	1120	Brown Lime	3602-1606 3604-1608
Shale	1755	Lansing	3615-1619 3616-1620
Lime & Shale	2090	Base Kansas City	3866-1870 3868-1872
Shale & Lime	2314	Viola	3963-1967 3963-1967
Lime & Shale	2450	Simpson	4025-2029 4028-2032
Shale & Lime	2857	Arbuckle	4065-2069 4067-2071
Lime & Shale	2977	Total Depth	4140-2144 4141-2145
Shale & Lime	3210		
Lime & Shale	3670		
Lime	3829		
Shale & Lime	3907		
Lime & Shale	3980		
Chert	4030		
Shale	4035		
Lime & Shale	4118		
Arbuckle Lime	4140 RTD		

DST #1 (S) 3795-3815, open 90 minutes with strong blow 90 minutes. Gas to surface in 35 minutes too small to measure. Recovered 1150' gassy oil and gas-cut muddy oil.
ISIP 1331#/30 min.
FSIP 1144#/30 min. still building
IFP 107#
FFP 275#

I hereby certify that this is a true and correct copy of the above mentioned well, to the best of my knowledge and belief.

John H. Knightley
and sworn to before me this

day of _____ 19____

Notary Public

My commission expires _____

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1971
CONSERVATION DIVISION
Wichita, Kansas