


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD 15-145-300892000

Pawnee County, Sec. 27 Twp. 23S Rge. (E) 15 (W)

Location as "NE/CNW/SW" or footage from lines C SW SW
Lease Owner Rains & Williamson Oil Co.
Lease Name GUYER Well No. 1
Office Address 1425 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 5 1965
Application for plugging filed October 5 1965
Application for plugging approved October 5 1965
Plugging commenced October 5 1965
Plugging completed October 5 1965
Reason for abandonment of well or producing formation no oil or gas found
in commercial quantities.

If a producing well is abandoned, date of last production - - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4055 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	280'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug & hulls @ 240', cement thru drill pipe with 30 sacks cement, mud back to 40', set solid bridge with plug and hulls and capped with 10 sacks cement, 2 sacks in rathole. Plugging completed @ 4:30 a.m. 10-5-65.

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1965

CONSERVATION COMMISSION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.
Address 1425 Wichita Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
1425 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of October, 1965

My commission expires January 8, 1968

Shirley Keck Notary Public.

ROTARY DRILLING LOG

15-145-30089-0000

OPERATOR: Rains & Williamson Oil Co.
#1 Guyer
C SW SW Section 27-23S-15W
Pawnee County, Kansas

CONTRACTOR: Rains & Williamson
Oil Co.

COMMENCED: 9-27-65

COMPLETED: 10-5-65

REMARKS: Set 280' of 8-5/8"
Surface Casing with 225
sacks GL3 cement.

FORMATIONS:

Surface Soil & Clay	25'
Sand	60'
Sand & Shale	225'
Shale	280'
Red Bed	951'
Anhydrite	970'
Shale & Shells	1290'
Shale & Lime	2180'
Lime & Shale	2360'
Shale & Lime	3528'
Lime & Shale	3650'
Lime	4055'

Rotary Total Depth (D&A) 4055'

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1965

CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and
correct to the best of our knowledge
and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State
of Kansas, County of Sedgwick, this 7th day of October, 1965.

My Commission Expires:
January 8, 1968

Shirley Keck
Shirley Keck, Notary Public