


15-145-30168-0000

WELL PLUGGING RECORD

Give All Information Completely,
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 28 Twp. 23 Rge. 15 (E) N (W)
Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner Anschutz Drilling Co., Inc.
Lease Name English Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 9 19 56
Application for plugging filed August 9 19 56
Application for plugging approved August 9 19 56
Plugging commenced August 9 4:30 P.M. 19 56
Plugging completed August 9 8:30 P.M. 19 56
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4203 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	297	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud to 270', set plug, dumped in 1/3 sack hulls, dumped in 20 sacks cement.

Filled hole to 35' with heavy rotary mud, set plug, dumped in 1/3 sack of hulls, dumped in 10 sacks cement.

RECEIVED
DIVISION
WICHITA, KANSAS

8-18-56

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF BARTON ss.
Donald W. Edwards (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Donald W. Edwards
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10 day of August 1956

My commission expires 6-25-59
Kenneth G. Fischer, Notary Public.

PLUGGING
FILE SEC. 28 T. 23 R. 15W
BOOK PAGE 89 LINE 25

15-145-30168-0000

DRILLERS LOG

English No. 1
Loc: NW NW SE
Sec: 28-23S-15W
Pawnee County, Kansas
Company: Anschutz Drilling Co., Inc.
Contractor: Honaker-Davis Drig. Co.

Conn: 7-24-56
Comp: 8- 9-56
Rotary Total Depth: 4203
Casing: 8-5/8" at 297
D & A

0	30	Surface Soil	
30	145	Sand & Gravel	8-5/8" casing cemented at
145	207	Shale & Shells	297' with 225 sacks cement
207	425	Red Bed & Shale	and 4 sacks calcium chloride
425	475	Sand	
475	940	Red Bed & Shale	
940	965	Anhydrite	
965	1225	Shale & Shells	
1225	1565	Shale, Shells & Salt	
1565	1780	Shale & Shells	
1780	1855	Shale & Lime Streaks	
1855	1980	Lime	
1980	2020	Shale, Anhydrite & Shells	
2020	2172	Lime (Sandy)	
2172	2370	Shale & Lime	
2370	2415	Lime & Shale	
2415	2655	Shale & Lime	
2655	3160	Lime & Shale	
3160	3215	Lime	
3215	3360	Lime & Shale (Topoka)	
3360	3500	Shale & Lime	
3500	3510	Lime & Shale	
3510	3511	Lime	
3511	3530	Shale	
3530	3649	Lime & Shale	
3649	3770	Lime	
3770	3834	Lime & Shale	
3834	3893	Lime	
3893	4006	Lime & Shale	
4006	4063	Conglomerate	
4063	4085	Conglomerate & Chert	
4085	4105	Chert & Lime	
4105	4120	Simpson & Shale	
4120	4173	Simpson, Shale & Sand	
4173	4203	Arbuckle	
4203		Total Rotary Depth	

RECEIVED
D & A STATE CORPORATION COMMISSION

AUG 13 1956

DIVISION

I certify that this is the true and correct copy of the above log to the best of my knowledge.

H. S. Forbes
H. S. Forbes

Subscribed and sworn to before me this 14th day of August, 1956.

Kenneth G. Fischer
Kenneth G. Fischer, Notary Public

My commission expires; 6-25-59

PLUGGING			
FILE	SEC. 28	T. 23	R. 15W
BOOK	PAGE 89	LINE 25	