

15-145-19052-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Pawnee County, Sec. 30 Twp. 23S Rge. 15W (X) (W)

Location as "NE/CNW/SW" or footage from lines C NW/4 NE/4

Lease Owner Dunne-Gardner Drilling Co., Inc.

Lease Name Stewart Well No. 1

Office Address 300 Schweiter Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 9, 19 62

Application for plugging filed May 9, 19 62

Application for plugging approved May 9, 19 62

Plugging commenced May 9, 19 62

Plugging completed May 9, 19 62

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? LacCamp - yes

Name of Conservation Agent who supervised plugging of this well LacCamp

Producing formation Depth to top Bottom Total Depth of Well 3060 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe		0	154	8-5/8"	5-4-62	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole with mud to 350'. Bottom plug @ 350' w/25 sacks cement. Fill hole with mud to 140'. Set plug w/20 sacks cement and 1/4 sack hulls. Top plug set at 35' w/10 sacks cement and 1/4 sack hulls.

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dunne-Gardner Drilling Co., Inc.

Address 300 Schweiter Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Don Gardner

(Employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Gardner

300 Schweiter Building, Wichita 2, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of May, 19 62

My commission expires November 9, 1965

Marilyn E. Fox
Notary Public.



15-145-19052-6080

DRILLER'S LOG

OPERATOR: Dunne-Gardner Drilling Co., Inc.
300 Schweiter Building, Wichita 2, Kansas

LEASE: Stewart

WELL: No. 1

LOCATION: C NW/4 NE/4 Sec. 30-23S-15W,
Pawnee County, Kansas

CONTRACTOR: Dunne-Gardner Drilling Co., Inc.

DATE COMMENCED: May 4, 1962

DATE COMPLETED: May 9, 1962

TOTAL DEPTH: 3060'

CASING: Set 8-5/8" surface pipe @ 154' with 180 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1962
CONSERVATION DIVISION
Wichita, Kansas

<u>FROM</u>	<u>TO</u>	
150	981	Shale
981	1015	Anhydrite
1015	1760	Shale and Shells
1760	1935	Shale and Lime
1935	2115	Lime
2115	3060	Lime and Shale
3060		Total Depth


I certify the above to be true and correct to the best of my knowledge and belief.

DUNNE-GARDNER DRILLING CO., INC.

By 
Don Gardner

Subscribed and sworn to before me this 21st day of May, 1962.

My Commission Expires:
November 9, 1965


Marilyn E. Fox, Notary Public