

15.185-01379-0000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JAN 6 1964  
1-6-64  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Don Moore Associates Inc.

Complete Address: 918 Central Bldg., Wichita, Kansas

Lease Name Isern-Bever Well No. # 1

Location NE NE NE Sec. 24 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3490

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Western Petroleum Co., Inc.

Address: 925 Patton, Great Bend, Kansas License No.     

Operation Completed: Hour 11:00AM Day 3rd Month Jan. Year 1964

The Above well was plugged as follows:

240' of 8 5/8" surface pipe, cemented with 260 sacks. Fluid level was  
up in hole. 1st cementing plug and 1/2 sack hulls was pushed to 230',  
cemented with 25 sacks, through the drill pipe. Hole was filled with  
drilling mud to 40', 2nd cementing plug, bridged with hulls, cemented  
with 10 sacks to base cellar. Rat hole bridged and cemented with 2  
sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 1/7/64  
INV. NO. 8420-W

Signed: Archie Elving  
Well Plugging Supervisor