

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 Bitting Building
Wichita, Kansas

FILE 47-40
Location C E $\frac{1}{2}$ SE $\frac{1}{4}$ SE $\frac{1}{4}$
Sec. 3 Twp. 21 Rge. 9W

I have today completed supervision of plugging of: T.D. 3355'

Well No. 1 Lease Jeter

Operator Ingling & Parker Address 708 4th Nat'l. Bank Bldg., Wichita, Kans.

Field _____ County Rice

Well Classification: Oil _____ Gas _____ Dry Hole Yes

(Describe briefly the manner in which well was plugged)

Shot 4 $\frac{1}{2}$ " casing off at 2200 feet.

Bridged hole at top of pipe and filled with 15 sacks cement.

Filled hole with rotary mud, bridged hole at bottom of surface
pipe and cemented with 10 sacks cement.

Bridged hole at top of surface pipe and cemented with 5 sacks.

Cut off surface pipe and welded plate below plow depth.

Expense incurred as follows:

Date _____ *Day _____ Mileage _____

Date _____ *Day _____ Mileage _____

Date _____ *Day _____ Mileage _____

PLUGGING
FILE SEC 3-21-74
BOOK PAGE 47 LINE 40

STATE CORPORATION COMMISSION
JUN 17 1943
CONSERVATION DIVISION
6-1743

Hotel, meals, etc. \$ _____

*Show as 1/4, 2/4, 3/4 or 4/4.

Paul Dunbar
Conservation Agent

P.O. 597, McPherson, Kansas Date 6-16-43

I was not notified when this hole was plugged so did not supervise the plugging. This filled in blank was furnished me by our plugging dept. Paul Dunbar