

15.159.00492.0000

Form CP-3  
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 9 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
~~XXXXXXXXXX~~  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Rains & Williamson Oil Co. Inc.

Complete Address: 1425 Wichita Plaza, Wichita, Kansas 67202

Lease Name Shuyler Well No. # 1

Location SW SW NE Sec. 3 Twp. 21 Rge. 9 (E) (W)

County Rice Total Depth 3482'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Russ Casing Pulling Inc.

Address: Great Bend, Kansas License No. # 623

Operation Completed: Hour 11 AM Day 5 Month 6 Year 69

The Above well was plugged as follows:

8 5/8"-265'-Circulated w/cement. 5 1/2"-3015'-Cemented. Top Perf. 2958'.  
Sand hole to 2930'. 5 Sax. cement 2930' to 2890'. Mud 2890' to 500'.  
Spotted 25 Sax. cement 500' thru 5 1/2"-pipe. Mud top cement to 250'.  
Spotted 25 Sax. cement 250' thru 5 1/2"-pipe. Mud top cement to 40'.  
Bridge at 40". 10 Sax, cement 40' to 0. Pulled 2321'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 6/9/69  
INV. NO. 9916-11