

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 1 1968

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Robert F. White 15-145-00007-0001

Complete Address 714 Union Center Wichita, Kansas 67202

Lease Name Hill Well No. 1

Location NE NW NW Sec. 31 Twp. 23 Rge. 15 (E) (W) X

County Pawnee Total Depth 4131

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knights Casing Pulling Co.

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 4 P Day 9 Month 1 Year 1968

The above well was plugged as follows:

Total Depth 4131' 8 5/8 csg set at 307' cwc 200 sc.

5 1/2 csg set at 4129' cw 100 sc cement.

PBTD 4074' Top perf. at 3033'

Pushed plug to 3000' poured 25' sand and dumped 5 sc cement with dump bailer.

Recov. 2380' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sc gel W/3 sc hulls and 100 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOLVED

Signed: R. W. F. Massey
Well Plugging Supervisor

DATE 1/11/68
INV. NO. 7096-W