

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 17 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-145-01457-0000

Operator's Full Name Cities Service Oil Co

Complete Address: Box 308 Great Bend, Kansas

Lease Name Frick Well No. 1

Location SW NE NE Sec. 32 Twp. 23 Rge. (E) (W) 15

County Pawnee Total Depth 4152

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling & Halliburton Co

Address: Great Bend, Kans License No. 49

Operation Completed: Hour 1PM Day 15 Month 7 Year 63

The Above well was plugged as follows:

8 5/8" 373' circulated with cement - 5 1/2" 4152' with 350 sax cement -  
PB 4060' perf 3979'.

Filled with sand to 3960', set 5 sax cement with dump bailer - pulled  
2024' 5 1/2" to 380', circulated hole with heavy gel mud through 5 1/2"  
(18 sax Gel), displaced 25 sax cement through 5 1/2" at 380', heavy mud  
to 35', set bridge and filled to bottom cellar with cement.

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7-17-63

INV. NO. 7424-W

Signed: [Signature]  
Well Plugging Supervisor