

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 15 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company 15-145-01386-0001

Complete Address: P.O. Box 308 Great Bend, Kansas

Lease Name Benson-SE Unit Tract 2 Well No. 3-W

Location NE NW NW Sec. 32 Twp. 23 Rge. 15 (E) (W) X

County Pawnee Total Depth 4131

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Southwest Casing Pulling Co. Inc.,

Address: Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 4 P Day 11 Month 7 Year 1968

The Above well was plugged as follows:

Total Depth 4131' 8 5/8 csg set at 392' cwc 250 sc.

5 1/2 csg set at 4131' cw 200 sc cement.

5 1/2 csg PBTB 4116' with top perf. at 3612'.

Top of fish at 3567' Filled 5 1/2 csg with sand to 3500'. Dumped 5 sc cem. W/dump bailer.

Recov. 2810' of 5 1/2 csg.

Mud to 385' Set plg and 10' rock to 375' and dumped 3 sc cement with dump bailer.

Bailed hole dry and dumped 5 yds readymix cement from (370-surface)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey  
Well Plugging Supervisor

DATE 7-15-68

INV. NO. 8107-W