

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 24 1975

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Northern Natural Gas Co. 15-145-20302-0000

Complete Address Box 25388, Tulsa, Oklahoma 74135

Lease Name Becker Well No. 2

Location C. NW Sec. 33 Twp. 23 Rge. (E) (W) 15

County Pawnee Total Depth 2165'

Abandoned Oil Well        Gas Well XX Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Pawnee Well Service, Inc.

Address Great Bend, Kansas License No. 633

Operation Completed: Hour 5 P Day 22 Month 10 Year 1975

The above well was plugged as follows:

Total Depth 2165' 7" csg set 272' cwc 150 sk.

4 1/2 csg set 2164' cw 35 sk cem.

4 1/2 csg PBTD 2050' with PFS (1982)

Filled 4 1/2 csg W/sd (2050-1950) dumped 4 sk cem W/dump bailer. (1950-1920)

Cutoff & recovered 1488' of 4 1/2 csg.

Pumped down 7" csg with 15 sk gel & water W/100 lbs hulls -released 7" plug &

pumped 100 sk comm cem by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey  
Well Plugging Supervisor

DATE 10/24/75

INV. NO. 2121-W