

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-145-20288-0000

RECEIVED
STATE CORPORATION COMMISSION
JUL 25 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Asperm Drilling Company
Complete Address Box 783, Great Bend, Kansas 67530
Lease Name Becker Well No. 1
Location NW SE SW Sec. 33 Twp. 23 Rge. (E) (W) 15
County Pawnee Total Depth 2961'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Russ Casing Pulling
Address Box 1082, Great Bend, Kansas 67530 License No. 623
Operation Completed: Hour 11: A Day 24 Month 7 Year 1974

The above well was plugged as follows:

Total Depth 2961' 8 5/8 csg set at 252' cwc 200 sk.

5 1/2 csg set at 2238' cw 125 sk cmt.

5 1/2 csg PBSD 2150' and top perf. (2111')

Filled 5 1/2 csg with sand (2150-2050) dumped 5 sk cmt With dump bailer. (2015-2050)

Cutoff and recovered 1725' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, -released 8 5/8 plug

& pumped 100 sk cmt by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo R. Massey
Well Plugging Supervisor

INVOICED

DATE 7/29/74

INV. NO. 9593-W