

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 3 1969
CONSERVATION DIVISION
Wichita, Kansas

15-145-60012-00-02

Operator's Full Name Icer Addis Oil Operations

Complete Address Box 519 Great Bend, Kansas

Lease Name Becker Well No. 1

Location SW SE NW Sec. 33 Twp. 23 Rge. (E) (W) 15

County Pawnee Total Depth 4050

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 3P Day 2 Month 10 Year 1969

The above well was plugged as follows:

Total Depth 4050' 8 5/8 csg set at 375' cwc

5 1/2 csg set at 4050' cw 150 sk cmt.

5 1/2 csg PBD 3840' Perf. (3779-3782)

Filled 5 1/2 csg W/sd (3760-3840) Dumped 5 sk cmt W/dump bailer.

Cutoff and recovered 2020' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 15 sk gel W/2 sk hulls, plug and 100 sk

50-50 poz cmt W/6% total gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/3/69

INV. NO. 582-4

Signed: Ben F. Mearns
Well Plugging Supervisor