

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
STATE OF KANSAS

AUG 3 1988
8-3-88
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 185 -22,535 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR F. G. Holl Company OPERATORS LICENSE NO. 5056
P.O. Box 780167
ADDRESS Wichita, KS 67678-0167 PHONE # (316) 684-8481

LEASE (FARM) McFarland WELL NO. 1-11 WELL LOCATION SE SE SE COUNTY Stafford
SEC. 11 TWP. 21S RGE. 11W (E) or (W) TOTAL DEPTH 3465' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A XX SWD or INJ WELL _____ DOCKET NO. _____
SURFACE CASING SIZE 8 5/8" SET AT 305.50' CEMENTED WITH 250 SACKS
CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS
PERFORATED AT _____

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Fill hole with heavy mud.

50 sacks at 510'; 40 sacks at 340'; 10 sacks 0 to 40'. 15 sacks in rathole. Use 60/40

Pozmix, 6% gel.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? _____
(If not, explain)

Top of Arbuckle 3429' - No porosity (tight)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN July 30, 1988, 12:45 AM

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Richard Mead PHONE # (316) 278-2131
P.O. Box 129
ADDRESS Sterling, KS 67579

PLUGGING CONTRACTOR Sterling Drilling Company LICENSE NO. 5142

ADDRESS P.O. Box 129, Sterling, KS 67579 PHONE # (316) 278-2131

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: F. A. Wuellner
(Operator or Agent)

DATE: August 1, 1988