

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

RECEIVED
STATE CORPORATION COMMISSION

JUN 27 1990

WELL PLUGGING APPLICATION FORM
(File One Copy)

CONSERVATION DIVISION
Wichita, Kansas

6-27-90

API NUMBER 15 - 185-22,687,0000 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR F. G. Holl Company OPERATORS LICENSE NO. 5056

P. O. Box 780167

ADDRESS Wichita, Kansas 67278-0167 PHONE # (316) 684-8481

LEASE (FARM) Schafer WELL NO. 7-11 WELL LOCATION C W/2 NW NW COUNTY Stafford

SEC. 11 TWP. 21S RGE. 11W (~~E) (W)~~ TOTAL DEPTH 3375' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A XX SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 277 KB CEMENTED WITH 225 SACKS

CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Fill hole with heavy mud, 50 sacks

cement at 550'; 50 sacks at 300'; 15 sacks at 60'; 15 sacks in rathole. Use

60/40 Pozmix with 6% gel.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 3:00 AM, June 24, 1990

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Vaughn Thompson

PHONE # (316) 278-2131

P. O. Box 129

ADDRESS Sterling, Kansas 67579

PLUGGING CONTRACTOR Sterling Drilling Company LICENSE NO. 5142

P. O. Box 129

ADDRESS Sterling, Kansas 67579 PHONE # (316) 278-2131

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Richard L. Mead

(Operator or Agent)
Richard L. Mead, President

DATE: June 26, 1990