

RECEIVED

JAN 21 2003
KCC WICHITA
1-21-03

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-185-23,129-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F.G. Holl Company, L.L.C KCC LICENSE # 5056

ADDRESS 9431 E. Central, P.O. BOX 780167 CITY Wichita, KS. 67278-0167

STATE Kansas ZIP CODE 67278-0167 CONTACT PHONE # (316) 684-8481

LEASE SCHAFFER "A" -11 WELL# 8-11 SEC. 11 T. 21 R. 11 (East/West)

C E/2 NE SW SPOT LOCATION/OOOO COUNTY Stafford

1890 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

2310 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE N/A SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 226'KB CEMENTED WITH 250 SACKS

PRODUCTION CASING SIZE 4-1/2" SET AT 3492'KB CEMENTED WITH 225 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3387' - 3391' Simpson Chert

ELEVATION 1744/1753 T.D. 3500' PBDT 3412' ANHYDRITE DEPTH 455'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Heavy Mud, Halls, Cement and plug according to KCC rules and regulations.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Rob Long

PHONE# () (620) 793-0915/786-5783 (cell)

ADDRESS P.o. Box 158 City/State Belpre, KS. 67519

PLUGGING CONTRACTOR Quality Well Service KCC LICENSE # 331925

ADDRESS 401 West Main, Lyson, KS. 67554 PHONE # () (620) 727-3410

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Not known

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 01/17/2003 AUTHORIZED OPERATOR/AGENT: Franklin R. Greenbaum
(signature)

6/03

8/03

RECEIVED
 JAN 21 2003
 KCC WICHITA

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
 Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG

Schafer 'A' 8-11

LOCATION: 60' S of C E/2 NE SW of Section 11 T 21s R 11w
API: 15-185-23129-0000 Stafford County, Kansas

OWNER: F.G. Holl Company, L.L.C.
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 07-Jun-01
COMPLETED: 14-Jun-01

TOTAL DEPTH: **DRILLER** 3500 FEET
LOGGER 3483 FEET

Ground Elevation: 1744
KB Elevation: 1753

LOG

0 -	2 FEET	Top Soil
2 -	6 FEET	Sandy Clay
6 -	15 FEET	Sand and Gravel
15 -	30 FEET	Clay
30 -	175 FEET	Sand and Gravel
175 -	430 FEET	Redbeds
455 -	476 FEET	Anhydrite
476 -	1260 FEET	Redbeds, Shales and Salt
1260 -	3420 FEET	Limestone, Shale and Dolomite
3420 -	3500 FEET	Arbuckle

CASING RECORDS

Surface Casing-8-5/8"

Spud @ 8:00 am on 6/7/01. Drilled 12-1/4" hole to 228'. Ran 5 joints of new 23# 8-5/8" surface casing, tally 215.19' set at 226' KB. Cemented with 250 sx 60/40 Poz, 2% Gel and 3% CC, Cement did circulate. Plug down at 12:15 pm on 6/7/01 by Acid Services. Ticket #03588.

Plugging Record

Ran 83 joints of used 10.5#, 4-1/2" casing. Tallied 3484', set @ 3492 KB. Cemented with 50 sx Lite and 175 sx 50/50 Poz with additives. Plugged rathole with 15 sx, mousehole with 10 sx, using A-Serv-Lite. Plug down at 11:45 pm on 6/14/01 by Acid Services. Ticket # 03440.

DEVIATION SURVEYS

1/4 degree(s) at	228	feet
3/4 degree(s) at	2662	feet
3/4 degree(s) at	3389	feet
3/4 degree(s) at	3500	feet



Kansas Corporation Commission

Kathleen Sebelius, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Holl, F.G., Company L.L.C.
9431 E Central, Suite 100
Wichita, KS 67206

January 22, 2003

Re: SCHAFFER A 11 #8-11
API 15-185-23129-00-00
E2NESW 11-21S-11W, 1890 FSL 2310 FWL
STAFFORD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888