

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-30348.0001

LEASE NAME Schafer

WELL NUMBER #4

 Ft. from S Section Line

 Ft. from E Section Line
SW SE NW

SEC. 11 TWP. 21S RGE. 11W (E) or (W)

COUNTY Stafford

Date Well Completed 9-20-66

Plugging Commenced 12-31-87

Plugging Completed 1-11-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F.G. Holl

ADDRESS 6427 E. Kellogg
Wichita, Kansas 67207

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3397'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	272'	none
				4-1/2"	3360'	1930'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3275' and 4 sacks cement. Shot pipe @ 2110', 1930', pulled a total of 61 joints of 4-1/2" casing. Plugged surface with 4 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug and 100 cement, 60/40 pos, 6% gel.
Plugging Complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 12th day of January 1988

Jane L. Linn Notary Public

My Commission Expires:



1-13-88

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1988
CONSERVATION DIVISION
Wichita, Kansas
Form CP-4
Revised 07-86

I S E R N D R I L L I N G C O M P A N Y

15.185.30348.0000

F. G. Holl's SCHAFFER #4
SW SE NW, Sec. 11-21S-11W
Stafford County, Kansas

ELEVATION: 1752' GL; 1754' DF; 1756' KB

9-13-66 Moving in rigging up.

9-14-66 Set 272' 8 5/8" at 272' with 225 sacks quick set, Sun Cementing Company. Cement did circ. Job completed 1:00 a.m.

9-15-66 Drilling at 1710'. DST #1 (3090 - 3150) 60' anchor.
Recovered 30' mud ISIP 170# in 20 min.
9-16-66 Drilling at 2435'. IF 71# in 5 min. FSIP 103# in 20 min.
FF 90# in 60 min.

9-17-66 Drilling at 2905'.

DST #2 (3352 - 3397) 45' anchor.

9-18-66 Drilling at 3150'.

9-19-66 Drilling at 3397'.

9-20-66 Set 106 jts. 4 1/2" casing 9:50# 8 rd thd at 3360' with 75 sacks cement. Job completed 11:55. ~~11:55~~

TOPS
Anhydrite 473'

C
O
P
Y

STATE COMMISSIONER OF MINES AND GEOLOGY

JUL 20 1987

OFFICE OF THE COMMISSIONER