



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ogle of Red Tiger Drlg. Co. has this
date requested permission to plug the following described well:

Mr. Ogle guarantees payment of the plugging fee.

Operator's full Name: L.V. Stan Bell

Complete Address: Suite 925 200 W. Douglas Wichita, Ks

Lease Name: Rugan Well No. 1

Location: SE/NE/NW Sec. 11 Twp. 21s Rge. 12 (E)(W) W

County: Stafford Total Depth 3497 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ogle was instructed to plug the well as follows:

294 ft of 8 5/8 surface pipe cemented with 275 sacks.

Pump 40 sacks cement to 700 ft. Second plug at 290 ft, & p

pump 30 sacks cement. Fill hole to 40 ft, plug, 1/2 sack

hulls, & 10 sacks cement to surface. 2 sacks cement in rat

hole. Sun Cementing Co. Great Bend, Ks.

Very truly yours,

L. Russell Biberstein
Conservation Division Agent