



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 23 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Baker of Red Tiger Drlg. Co. has this
date requested permission to plug the following described well:

Mr. Baker guarantees payment of the plugging fee.

Operator's full Name: L.V. Stan Bell

Complete Address: 562 Westmore Court Wichita, Ks

Lease Name: Holl Well No. 2

Location: SE/NW/NE Sec. 11 Twp. 21s Rge. 12 (E)(W) W

County: Stafford Total Depth 3080 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Baker was instructed to plug the well as follows:

291 ft of 8 5/8 surface pipe cemented with 275 sacks. Fill
hole to 550 ft, plug, 50 sacks cement, second plug at 280 ft,
35 sacks cement. Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks
cement to surface. 2 sacks cement in rat hole.

Pumped by Sun Oil Co. Great Bend, Ks

Very truly yours,

U. Russell Biberstein
Conservation Division Agent