



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

March 14, 1968.

Dear Sir:

Mr. Buck Smith of Glen & Smith Pipe Pulling Co. has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Bea Drilling Company

Complete Address: P.O. Box 247 Ellinwood, Kansas. 67526

Lease Name: Laudick "C" Well No. #1

Location: SW-SW-SE Sec. 16 Twp. 21 Rge. 12W (E) (W) W

County: Stafford Total Depth 3575' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:

280 ft. of 8 5/8" surface pipe circulated with 200 sacks cement.
Top perforation 3254 1/2 ft. Sand to 3240 ft. & 3 sacks cement.
Mud to 280 ft. 10 ft. rock bridge. 5 sacks cement as overnite
bridge. Hole bailed down & 20 sacks cement. Mud to 40 ft.
10 ft. rock bridge & 10 sacks cement to surface. 3020 ft of
5 1/2" pipe recovered.

Very truly yours,

Herman Gustafson
Conservation Division Agent