

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 145-30155-00-01 (of 6th 18th well)
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1977
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Oil Properties Co., Inc.

Complete Address Box 246, Augusta, Kansas 67010

Lease Name Grizzell-Praeger (QWQ) Well No. 1

Location NW NW NW Sec. 23 Twp. 23 Rge. (E) (W) 15

County Pawnee Total Depth 4127'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated Kelso Casing Pulling

Plugging Contractor Kelso Casing Pulling 67524

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 10 A Day 19 Month 5 Year 1977

The above well was plugged as follows:

Total Depth 4127' 8 5/8 csg set 300' cwc 260 sk.

4 1/2 csg set 4125' W/150 sk cem.

4 1/2 csg PBD 3965' with perf. (3730'-3735')

Filled 4 1/2 csg with sand (3965'-3700') dumped 4 sk cem W/dump bailer. (3700'-3640')

Cutoff & recovered 2025'.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 25 sk gel & water, released plug & 120 sk 60/40 poz & shutin. FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Messing
Well Plugging Supervisor

DATE 5-24-77

INV. NO. 5210-4