

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 29 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name D. R. Lauck Oil Company, Inc. 15-145-00520-0000

Complete Address 301 South Broadway Wichita, Kansas 67202

Lease Name Guyer Well No. I

Location SW NE NE Sec. 25 Twp. 23 Rge. (E) (W) 15

County Pawnee Total Depth 4141

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Glenn & Smith Pipe Pulling Company

Address Box 156 Ellinwood, Kansas License No. 396

Operation Completed: Hour 10 A Day 24 Month 11 Year 1971

The above well was plugged as follows:

Total Depth 4141' 8 5/8 csg set at 257' cwc180 sk.

5 1/2 csg set at 4141' cw 1350 gal Latex. Top of cement 3525'

5 1/2 csg FBTD 4086' with top perf. (3805')

Set 5 1/2 wood plug at 3800' -poured 10' sd -dumped 5 sk cmt W/dump bailer. (3750-3800)

Cutoff and recovered 2885' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released plug

and pumped 100 sk 50-50 poz W/2% total gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. F. Mearns  
Well Plugging Supervisor

DATE 12-1-71

INV. NO. 4706-4