

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Specter Pipe & Supply, Inc. 15-145-80804-0000

Complete Address Box 169 Russell, Kansas 67665

Lease Name Garvin Well No. 6

Location SW SE SW Sec. 30 Twp. 23 Rge. (E) (W) 15

County Pawnee Total Depth 3995'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Lynch Casing Pulling Co.

Address Great Bend, Kansas License No. 457

Operation Completed: Hour 4:30 P Day 23 Month 11 Year 1970

The above well was plugged as follows:

Total Depth 3995' 8 5/8 csg set at 287' cwc

5 1/2 csg set at 3995' cw 150 sk cmt.

Set 5 1/2 wood plug at 3600' poured 10' sd and dumped 5 sk cmt W/dump bailer. (3550-3600)

Shutoff and recovered 2990' of 5 1/2 csg.

Pumped 20 sk gel W/3 sk hulls -plug and 100 sk reg poz 6% gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messing
Well Plugging Supervisor

DATE 12/1/70

INV. NO. 2932-11