

KANSAS

Form CP-3
Rev. 6-4-68

W
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Specter Pipe & Supply, Inc. 15-145-60803-0000
Complete Address Box 169 Russell, Kansas 67665
Lease Name Garvin Well No. 5
Location NE SE SW Sec. 30 Twp. 23 Rge. (E) (W) 15
County Pawnee Total Depth 3991
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Lynch Casing Pulling Co.
Address Great Bend, Kansas License No. 457
Operation Completed: Hour 12:30 P Day 23 Month 11 Year 1970

The above well was plugged as follows:
Total Depth 3991' 8 5/8 csg set at 299' cwc
5 1/2 csg set at 3991' cw 150 sk cmt.
Set 5 1/2 wood plug at 3600' poured 10' sd, dumped 5 sk cmt W/dump bailer. (3550-3600)
Cutoff and recovered 2571' of 5 1/2 csg.
Pumped 20 sk gel W/3 sk hulls - plug and 100 sk poz 6%.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo A. Murray
Well Plugging Supervisor

DATE 12/1/70
INV. NO. 2931-W