

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bldg Building
Wichita, Kansas

Stafford County, Sec. 8 Twp. 21S Rge. 14 W (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW NW SW

Lease Owner Vickers Petroleum Co., Inc.

Lease Name Weber Well No. 1

Office Address 201 WKH Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 20 19 51

Application for plugging filed December 20 19 51

Application for plugging approved December 20 19 51

Plugging commenced December 21 19 51

Plugging completed December 21 19 51

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough, Great Bend, Kansas

Producing formation Arb. Lime Depth to top 3686 Bottom 3700 Total Depth of Well 3700 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	877	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged with 1st plug at 270' 15 sx cement
Thru drill pipe - top plug at 35' 10 sx cement

12-28-51

REC 28 1951

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jayhawk Drilling Co., Inc.
Address 201 WKH Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
John M. Little (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John M. Little
201 WKH Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of December, 19 51
Allen J. Duster
Notary Public.

My commission expires August 13, 1953

23-8390-s 6-51-20M
PLUGGING
FILE SEC 8 21 R 140
BOOK PAGE 123 LINE 27

THE VICKERS PETROLEUM CO., INC.

Weber Well #1
NW NW SW Sec. 8-21S-14W
Stafford County, Kansas

Casing Record
8 5/8" @ 877' w/ 400 sx

Commenced: December 8, 1951
Completed: December 21, 1951

Elevation: 1939 R.B.
D. & A.

LOG

Sand & Soil	0- 70
Sand & Shale	70-310
Sand	310- 440
Sand, Shale, Shells, Red Beds	440- 760
Red Beds, Shale & Shells	760- 872
Anhydrite	872- 895
Red Beds, Shale, Shells	895-1375
Shale & Salt	1375-1505
Salt, Shale & Shells	1505-1600
Lime, Shale & Sand	1600-1685
Lime	1685-1790
Lime & Shale	1790-1920
Lime, Shale & Sand	1920-2070
Lime	2070-2165
Lime & Shale	2165-3145
Lime	3145-3208
Lime & Shale	3208-3344
Shale & Lime	3344-3598
Chert	3598-3631
Shale & Sand	3631-3686
Dolomite	3686-3700 T.D.

Drill Stem Test 3472-3487 open 15 min.
Weak blow Recovered 4' mud B.H.P. 1250#

Drill Stem Test 3690-3700 open 22 min.
Strong blow Recovered 980' Sulphur water
B.H.P. 1170#

D & A

SAMPLE TOPS

Heebner	3241
Brown Lime	3344
Lansing	3353
Viola	3598
Simpson Shale	3631
Arbuckle	3686

I hereby certify that this log is true and correct to the best of my knowledge and belief.


THE VICKERS PETROLEUM CO., INC.

BY Lyle Thomas

Subscribed and sworn to before me this 24th day of December, 1951.

Allen J. Denton
Notary Public

My Commission Expires August 13, 1953



STAT
DEC 28 1951
COMMISSION