

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County, Sec. 8 Twp. 21 Rge. 14 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE SE

Lease Owner Lee Phillips Oil Company

Lease Name Taylor Well No. 1

Office Address 1407 Union Nat'l Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 18 19 56

Application for plugging filed " 18 19 56

Application for plugging approved " 18 (verbally) 19 56

Plugging commenced " 18 19 56

Plugging completed " 18 19 56

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|------|--------|--------|------------|
| Surface | | 0 | 590' | 8 5/8" | 590' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole from TD to 300' with mud. Set plug at 300' with 20 sacks of cement on top. Heavy mud to 40' with plug set at 40' and 10 sacks of cement on plug.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Harms-Burt Drilling Company
Address Box 184, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. L. E. Phillips, Jr.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) *L. E. Phillips, Jr.*

(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of May, 19 56

Nelle A. Salmon
Nelle A. Salmon Notary Public.

My commission expires October 4, 1957

PLUGGING
FILE SEC 8 T. 21 R. 14W
BOOK PAGE 63 LINE 9

RECEIVED
STATE CORPORATION COMMISSION
MAY 29 1956
CONSERVATION DIVISION
Wichita, Kansas

5-29-56

DRILLERS LOG

Company : Lee Phillips Oil Co.

NE NE SE Section 8-21-14W
Stafford County, Kansas

Farm: Taylor #1

Commenced: May 7, 1956

Completed: May 10, 1956

Elevation: 1942 KB

| | |
|-------------|----------------------|
| 0 - 40 | soil |
| 40 - 195 | sand |
| 195 - 300 | shale |
| 300 - 380 | sand |
| 380 - 590 | red bed |
| 590 - 871 | shale & sand |
| 871 - 1525 | shale & shells |
| 1525 - 1715 | shale, shells & lime |
| 1715 - 1885 | lime & shale |
| 1885 - 2250 | lime |
| 2250 - 2555 | shale & lime |
| 2555 - 3085 | lime & shale |
| 3085 - 3093 | lime & chert |
| 3093 - 3314 | lim |
| 3314 - 3335 | lime & shale |
| 3335 - 3345 | Brown Lime |
| 3345 - 3580 | lime |
| 3580 - 3620 | lime & chert |
| 3620 - 3632 | lime |
| 3632 - 3641 | Simpson Sand |
| 3641 - 3652 | lime & chert |
| 3652 - 3677 | shale & lime |
| 3677 - 3709 | Arbuckle Lime |
| 3709 | T.D. |

Set 590' 8 5/8" surface pipe, cemented with 200 sacks of common cement & 3 sacks of calcium chloride.

Tops: Brown Lime - 3335
 Lansing KC - 3345
 Simpson Sand - 3632
 Arbuckle - 3677

22 1/2
 12 1/2

 14 03

Drill Stem Test: #1 3581 - 3606 Open 1 hour. Shut in 20 min.
Rec. 9' mud. OF BHP

#2 3633 - 3641 Open 1 hour. Shut in 20 min.
Rec. 2190' of water
IFP-3354 FFP-1010 DHP-1010#

Dry, plugged & abandoned.

STATE OF Kansas COUNTY OF Barton, ss.

allan harms (employee or owner) of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and that the same are true and correct.

(Signature) Allan Harms
Harms - Best Drilling Co.
Box 184 Great Bend Kansas

Subscribed and sworn to before me this 25 day of May 1956

Mary E Van Telt
Notary Public

My commission expires 1-20-58

| | | | |
|----------|------|------------|--|
| PLUGGING | | | |
| FILE | SEC | T 21 R 14W | |
| BOOK | PAGE | 63 LINE 9 | |

MAY 2 1956
CONSERVATION DIVISION
Topeka, Kansas